



PO Box 884, Chanute, KS 66720  
 120-431-9210 or 800-487-8678

TICKET NUMBER 30030

LOCATION Eureka

FOREMAN Troy Strickler

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-9-10	4758	Hummer 160-28				Wilson
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Layne Energy			445	John		
MAILING ADDRESS			477	Shannon		
P.O. Box 160			437	Jim		
CITY	STATE	ZIP CODE				
Sycamore	Ks					

JOB TYPE L/S 0 HOLE SIZE 6 3/4" HOLE DEPTH 1277' CASING SIZE & WEIGHT 4 1/2"  
 CASING DEPTH 1220' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 13.4" SLURRY VOL 42031 WATER gal/ok 8" CEMENT LEFT IN CASING 0'  
 DISPLACEMENT 19.4341 DISPLACEMENT PSI 600 MIX PSI 1100 RATE \_\_\_\_\_

REMARKS: Rig up to 4 1/2" casing. Break circulation w/ 10 bbl fresh water  
 Pump 10sk Gel-Flud w/ hulls, 5 bbl water spacer, 20 bbl Caustic Soda Pre-Flush,  
 10 bbl Dry water. Mixed 1350kg thick set cement w/ 8" Kal-Seal 10k, 1/2"  
 Phenoresol 1sk, 1/2" FL-110 + 1/2" CAF-38 @ 13.4"/gal. Workover Pump + liner  
 Release Plug. Displace w/ 8bl fresh water. Final Pumping Pressure 600 PSI.  
 Pump Plug to 1100 PSI. wait 2mins. Release Pressure. Float Hold.  
 Good Cement to surface = 6 bbl slurry to pit.

*Job Complete*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	925.00	925.00
5406	40	MILEAGE	3.65	146.00
1126A	1353kg	Thick set Cement	17.00	2299.00
1110A	1080 #	8" Kal-Seal 10k	.42	453.60
1107A	17 #	1/2" Phenoresol	1.15	19.55
1135	68 #	1/2" FL-110	2.50	170.00
1146	34 #	1/2" CAF-38	7.70	261.80
1118B	500 #	Gel-Flud	.20	100.00
1105	50 #	Hulls	.39	19.50
1103	100 #	Caustic Soda	1.45	145.00
5407A	7.43	Ton mileage	1.20	891.60
5502C	4hrs	800W Vac Truck	85.00/hr	340.00
4404	1	4 1/2" Top Rubber Plug	45.00	45.00
1121	3000 gal	Curb Water	14.90/100	44.70
			Subtotal	5661.74
			SALES TAX	245.33
			ESTIMATED TOTAL	5907.07

AUTHORIZATION [Signature] TITLE DCM-Forman DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form