

Lease:	NORTH EAST BAKER	
Owner:	BOBCAT OILFIELD SERVICES INC	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20FT, 6IN	5 SACKS	8 3/4
Longstring 330' 2 7/8 8RD	Cemented: 50	Hole Size: 5 5/8

Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: F-9
Location: NW, SW, NW, SE, S5, T20, SR23, E
County: LINN
FSL: 1,875 1862
FEL: 2,475 2488
API#: 15-107-24438-00-00
Started: 3-29-11
Completed: 3-30-11


SN: 266	Packer:	TD: 340'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOPSOIL			
25	26	LIME			
3	29	SHALE			
3	32	BLACKSHALE			
19	51	LIME			
3	54	SHALE			
2	56	BLACKSHALE			
14	70	LIME (SHALEY)			
1	71	BLACKSHALE			
10	81	SANDY SHALE (LIMEY) (FLOW) (WATER&GAS)			
32	113	SHALE			
9	122	SANDY SHALE (DRY SAND)			
94	216	SHALE			
1	217	BLACKSHALE			
10	227	SHALE			
6	233	LIME			
20	253	SHALE			
1	254	LIME			
4	258	SHALE			
8	266	LIME			
2	268	SANDY SHALE (OIL SAND STK)(WATER)			
2	270	OIL SAND (WATER)			
43	273	OIL SAND (SOME SHALE) (WATER) (POOR BLEED)			
1	274	OIL SAND ("WATER") (VERY LITTLE OIL) (VERY FRACTURED)			
3	277	OIL SAND ("WATER") (VERY LITTLE OIL)			
1	278	OIL SAND (OIL & WATER) (SOME SHALE) (GOOD BLEED)			
1	279	LIME			
2	281	OIL SAND (LIMEY) (GOOD BLEED)			
6	287	OIL SAND (GOOD BLEED) (SOME SHALE)			
3.5	290.5	SANDY SHALE (OIL SAND STK)			
4.5	295	OIL SAND (VERY SHALEY) (FAIR BLEED)			
6	301	OIL SAND (GOOD BLEED)			
13	314	SHALE			
2	316	COAL			
4	320	SHALE			
11	331	LIME (SHALEY)			
TD	340	SHALE			

SURFACE: 3-29-11-JUDY
 SET TIME: 4:00 P.M.
 CALLED: 12:30 P.M.

LONGSTRING: 330' 2 7/8 8RD PIPE
 TD: 340'
 SET TIME: 2:00 P.M. -JUDY
 CALLED: 12:30 P.M.



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: F-9
Location: NW, SW, NW, SE, S5, T20, SR23, E
County: LINN
FSL: 1,875 1862
FEL: 2,475 2488
API#: 15-107-24438-00-00
Started: 3-29-11
Completed: 3-30-11

Core Run #1

Lease :	NORTH EAST BAKER
Owner:	BOBCAT OILFIELD SERVICES INC.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	273		-----	OIL SAND ("WATER") (VERY LITTLE OIL) (VERY FRACTURED)	274
1	274		1	OIL SAND ("WATER") (VERY LITTLE OIL)	277
2	275		.5		
3	276		1		
4	277		.5	OIL SAND (OIL & WATER) (GOOD BLEED)	278
5	278		1	LIME	279
6	279		1	OIL SAND (LIMEY) (GOOD BLEED)	281
7	280		2		
8	281		1.5		
9	282		3.5		
10	283		2.5	OIL SAND (SOME SHALE) (GOOD BLEED)	287
11	284		1		
12	285		.5		
13	286		1		
14	287			SANDY SHALE (OIL SAND STREAKS) (POOR BLEED)	290.5
15	288				
16	289				
17	290				
18	291			OIL SAND (VERY SHALEY) (FAIR BLEED)	
19	292				
20	293				

Avery Lumber

P.O. BOX 66
MOUND CITY, KS 66056
{913} 795-2210 FAX {913} 795-2194

Customer Copy
INVOICE
PLEASE REFER TO INVOICE NUMBER
ON ALL CORRESPONDENCE

Page: 1		Invoice: 10029149	
Special :		Time:	12:23:42
Instructions :		Ship Date:	03/17/11
		Invoice Date:	03/21/11
Sale rep #:	MAVERY MIKE	Acct rep code:	Due Date: 04/05/11
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823	
Customer #:	3570021	Customer PO:	Order By: TERRY

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
315.00	315.00	L	BAG	CPPC	PORTLAND CEMENT	7.9900 BAG	7.9900	2516.85
200.00	200.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.1000 BAG	5.1000	1020.00
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

*NE Baker
F-9*

*DIRECT DELIVERY - 3.21.11
ORDERED BY TERRY*

913.837.4159

INVOICE

	FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____ SHIP VIA LINN COUNTY RECEIVED COMPLETE AND IN GOOD CONDITION X	Taxable 3774.85 Non-taxable 0.00 Tax # _____	Sales total \$3774.85 Sales tax 237.82 TOTAL \$4012.67
--	--	--	---

2 - Customer Copy

