

Lease:	NORTH EAST BAKER	
Owner:	BOBCAT OILFIELD SERVICES INC	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20FT, 6IN	5 SACKS	8 3/4
Longstring	Cemented:	Hole Size:
332' 2 7/8 8RD	50	5 5/8

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: F-10
Location: N2, SW, NW, SE, S5, T20, SR23, E
County: LINN
FSL: 1,875 1852
FEL: 2,310 2154
API#: 15-107-24376-00-00
Started: 3-30-11
Completed: 3-31-11

SN: 270'	Packer:
Plugged:	Bottom Plug:


TD: 340

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOPSOIL			
29	30	LIME			
3	33	SHALE			
3	36	BLACKSHALE			
2	38	SHALE			
18	56	LIME			
2	58	SHALE			
2	60	BLACKSHALE			
13	73	LIME (SHALEY)			
1	74	BLACKSHALE (FLOW) (WATER & GAS)			
10	84	SHALE (LIMEY) (FLOW)(WATER & GAS)			
30	114	SHALE			
14	128	SANDY SHALE (DRY SAND)			
99	227	SHALE			
1	228	BLACKSHALE			
3	231	SHALE			
6	237	LIME			
21	258	SHALE			
2	260	LIME			
3	263	SHALE			
7	270	LIME			
3	273	SANDY SHALE (LIMEY) (ODOR)			
3	276	OIL SAND (SOME SHALE) (WATER) (POOR BLEED)			
1	277	OIL SAND (SHALEY) (SOME WATER) (POOR BLEED)			
2	279	OIL SAND (FAIR BLEED)			
1	280	OIL SAND (SOME SHALE) (FAIR BLEED)			
2	282	OIL SAND (SOME SHALE) (GOOD BLEED) (LITTLE SHOW OF WATER)			
.5	282.5	LIME			
1	292.5	OIL SAND (SOME SHALE) (GOOD BLEED)			
3	295.5	OIL SAND (SHALEY) (GOOD BLEED)			
3.5	299	SANDY SHALE (SOME OIL SAND STEAKS) (POOR BLEED)			
1	300	OIL SAND (FAIR BLEED) (OIL & WATER)			
1.5	301.5	SANDY SHALE (SOME OIL SAND STEAKS) (POOR BLEED)			
1.5	303	OIL SAND (SHALEY) (FAIR BLEED) (SOME GAS)			
4	307	OIL SAND (SOME SHALE) (GOOD BLEED)			
10	317	SHALE			
2	319	COAL			
5	324	SHALE			
10	334	LIME			
TD	340	SHALE			

SURFACE: 3-30-11-JUDY
SET TIME: 4:00 P.M.
CALLED: 12:30 P.M.

LONGSTRING: 332' 2 7/8 8RD PIPE
SET TIME: 2:00 P.M. 3-31-11-RUSSEL
CALLED: 11:30 A.M.



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: F-10
Location: N2, SW, NW, SE, S5, T20, SR23, E
County: LINN
FSL: 1,875 1852
FEL: 2,310 2154
API#: 15-107-24376-00-00
Started: 3-30-11
Completed: 3-31-11

Lease :	NORTH EAST BAKER
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	280		-----		
1	281		1	OIL SAND SOME SHALE (GOOD BLEED) (LITTE SHOW OF WATER)	282
2	282		1	LIME	282.5
3	283		1.5		
4	284		1.5	OIL SAND (SOME SHALE) (LITTEL SHOW OF WATER) (GOOD BLEED)	
5	285		1.5		286
6	286		2		
7	287		1		
8	288		1.5		
9	289		1.5	OIL SAND (SOME SHALE) (GOOD BLEED)	
10	290		1		291
11	291		2	LIME	291.5
12	292		2	OIL SAND (SOME SHALE) (GOOD BLEED)	292.5
13	293		2.5		
14	294		2	OIL SAND (SHALEY) (GOOD BLEED)	
15	295		2		295.5
16	296		2		
17	297		1.5	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	
18	298		2		299
19	299		2		
20	300		1.5	OIL SAND (FAIR BLEED) (OIL & WATER)	

Avery Lumber

P.O. BOX 66
MOUND CITY, KS 66056
(913) 795-2210 FAX (913) 795-2194

Customer Copy
INVOICE
PLEASE REFER TO INVOICE NUMBER
ON ALL CORRESPONDENCE

Page: 1		Invoice: 10029149	
Special :		Time:	12:23:42
Instructions :		Ship Date:	03/17/11
		Invoice Date:	03/21/11
Sale rep #:	MAVERY MIKE	Acct rep code:	Due Date: 04/05/11
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823	
Customer #:	3570021	Customer PO:	Order By: TERRY

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
315.00	315.00	L	BAG	CPPC	PORTLAND CEMENT	7.9900 BAG	7.9900	2516.85
200.00	200.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.1000 BAG	5.1000	1020.00
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

INVOICE

NE Baker
F-10

DIRECT DELIVERY — 3.21.11
ORDERED BY TERRY

913.837.4155

	FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____	Sales total \$3774.85
	SHIP VIA LINN COUNTY	
	RECEIVED COMPLETE AND IN GOOD CONDITION	
X		Taxable 3774.85 Non-taxable 0.00 Tax # _____ Sales tax 237.82

TOTAL \$4012.67

2 - Customer Copy

