

Lease:	NORTH EAST BAKER	
Owner:	BOBCAT OILFIELD SERVICES INC.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20FT, 6IN	5 SACKS	8 3/4
Longstring	Cemented:	Hole Size:
325' 2 7/8 8RD PIPE	50	5 5/8

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: F-14
Location: N2,SW,NE,SE,S5,T20,SR23,E
County: LINN
FSL: 1,875 1840
FEL: -990 834
API#: 15-107-24380-00-00
Started: 4-6-11
Completed: 4-7-11


SN: 263'	Packer:	TD: 330'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOPSOIL			
11	12	LIME			
4	16	SHALE			
2	18	BLACKSHALE			
24	42	LIME			
3	45	SHALE			
2	47	BLACKSHALE			
14	61	LIME (SHALEY)			
1	62	BLACKSHALE			
10	72	SHALE (LIMEY)			
31	103	SHALE			
23	126	SANDY SHALE (DRY SAND)			
88	214	SHALE			
1	215	BLACKSHALE			
3	218	SHALE			
7	225	LIME			
22	247	SHALE			
12	259	LIME			
4.5	263.5	SHALE			
6.5	270	OIL SAND (FAIR BLEED) (SHALEY)			
3.5	273.5	OIL SAND (SHALEY)(FAIR BLEED)			
6	279.5	SANDY SHALE (SOME OIL SAND STEAKS)(POOR BLEED)			
2.5	282	OIL SAND (SHALEY)(FAIR BLEED)			
1	283	SANDY SHALE (SOME OIL SAND STEAKS)(POOR BLEED)			
1.5	284.5	OIL SAND (VERY SHALEY) (GOOD BLEED)			
2.5	287	OILS SAND (SOME SHALE) (GOOD BLEED)			
5	292	SANDY SHALE			
3	295	OIL SAND (SHALEY)(FAIR BLEED)			
12	307	SHALE			
2	309	COAL			
5	314	SHALE			
10	324	LIME			
TD	330	SHALE			

SURFACE: 4-6-11
SET TIME: 4:00 P.M. -BECKY
CALLED: 1:00 P.M.

LONGSTRING: 325' 2 7/8 8RD PIPE
TD: 330'
SET TIME: 2:00 P.M. - 4-7-11
CALLED: 12:00 P.M. - RUSSEL



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: F-14 <i>NE</i>
Location: <i>N2,SW,NE,SE,S5,T20,SR23,E</i>
County: LINN
FSL: 1,875 <i>1840</i>
FEL: -990 <i>834</i>
API#: 15-107-24380-00-00
Started: 4-6-11
Completed: 4-7-11

Lease :	NORTH EAST BAKER
Owner:	BOBCAT OILFIELD SERVICES INC.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	271		-----		
1	272		1.5	OIL SAND (SHALEY) (FAIR BLEED)	273.5
2	273		1.5		
3	274		1.5		
4	275		1.5		279.5
5	276		2	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	
6	277		1.5		
7	278		1.5		
8	279		2		
9	280		1	OIL SAND (SHALEY)(FAIR BLEED)	282
10	281		2		
11	282		2.5	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	283
12	283		2	OIL SAND (VERY SHALEY) (GOOD BLEED)	284.5
13	284		2		
14	285		1.5	OIL SAND (SOME SHALE) (GOOD BLEED)	287
15	286		1.5		
16	287		1.5		
17	288		2.5		SANDY SHALE
18	289		3		
19	290		3.5		
20	291		3		

Avery Lumber

P.O. BOX 66
MOUND CITY, KS 66056
(913) 795-2210 FAX (913) 795-2194

Merchant Copy
INVOICE
THIS COPY MUST REMAIN AT
MERCHANT AT ALL TIMES!

Page: 1		Invoice: 10029555	
Special :		Time:	15:16:58
Instructions :		Ship Date:	03/30/11
:		Invoice Date:	04/01/11
Sale rep #:	MAVERY MIKE	Acct rep code:	Due Date: 05/05/11
Sold To: BOBCAT OILFIELD SRVC,INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC,INC (913) 837-2823 (913) 837-2823	
Customer #:	3570021	Customer PO:	Order By: TERRY

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	7.9900 BAG	7.9900	2237.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.1000 BAG	5.1000	1224.00
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

5TH
T 28

popimg01

INVOICE

ordered by Terry
Direct Delivery

NE Baker
F-14

913-837-4159

	FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____ SHIP VIA LINN COUNTY RECEIVED COMPLETE AND IN GOOD CONDITION X		Sales total \$3699.20 Taxable 3699.20 Non-taxable 0.00 Tax # _____ Sales tax 233.05
TOTAL			\$3932.25

1 - Merchant Copy

