



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 32795

LOCATION Ottawa KS

FOREMAN Fred Mader

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8/31/11	8147	Taylor-Bird # T-8	NE 23	8 23	21 23	LV
CUSTOMER Thomas Well Service			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS P.O. Box 97			506 FREMAD Safety Mdr			
CITY STATE ZIP CODE Ma Louth KS 66054			495 CASKEN CLK 0			
			505/7106 ARLMCD 2 ARLM			
			558 TIM LEM 510 BERMAS DM			
JOB TYPE <u>Long string</u>	HOLE SIZE <u>6 3/4</u>	HOLE DEPTH <u>1398'</u>	CASING SIZE & WEIGHT <u>5 1/2"</u>			
CASING DEPTH <u>1398'</u>	DRILL PIPE	TUBING	OTHER			
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING <u>4 1/2" Plug</u>			
DISPLACEMENT <u>22.16 BBL</u>	DISPLACEMENT PSI	MIX PSI	RATE <u>5 BPM</u>			

REMARKS: Establish rate. Mix Pump 15 BBL Flush w/ 1 Gal ESA-41. Mix Pump 25 BBL Talltale dye. Follow with SKS 50/50 Poz Mix Cement 6% Gal. Tail in w/ 45 sks OWC Cement. Flush pump + lines clean. Displace 4 1/2" Rubber plug to casing TD w/ 22.16 BBLs Formation Water Pressure to 800* PSI. Release pressure to set float valve. Check plug depth w/ wireline.

Customer Supplied Brine water Flush Plug Fluid.

Fred Mader

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	975 ⁰⁰
5406	65mi	MILEAGE	495	260 ⁰⁰
5402	1396'	Casing footage		71C
5407	Minimum	Ton Miles	558	330 ⁰⁰
5407	329.75	Ton Miles	570	415 ⁴⁹
5501C	5 hrs	Transport	505/7106	560 ⁰⁰
1124	114 sks	50/50 Poz Mix Cement		1191 ³⁰
1126	45 sks	OWC Cement		805 ⁵⁰
1118B	575 [#]	Premium Gel		115 ⁰⁰
1143	1 Gal	ESA-41		40 ⁴⁰
4404	1	4 1/2" Rubber Plug		45 ⁰⁰
			7.3%	SALES TAX 160 ⁴⁰
				ESTIMATED TOTAL 4898 ⁰⁹

243947

AUTHORIZATION Du Jhm

TITLE Prz Alli-Bobb

DATE 8-31-11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.