



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 32801
LOCATION Oftawa KS
FOREMAN Fred Maden

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9/2/11	8147	Taylor-Bird # T-9	NE 23	8	21	LV

CUSTOMER
Thomas Well Service

MAILING ADDRESS
P.O. Box 97

CITY McLouth STATE KS ZIP CODE 66

TRUCK #	DRIVER	TRUCK #	DRIVER
506	FIRE MAD	Safety Mtg	
495	CASKEN	CK	
510	GARMOD	GM	
548	DERMAS	505/T106	HARBEC

JOB TYPE Longstring HOLE SIZE 6 3/4 HOLE DEPTH 1418 CASING SIZE & WEIGHT 4 1/2"

CASING DEPTH 1415' DRILL PIPE _____ TUBING _____ OTHER _____

SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 4 1/2 Plug

DISPLACEMENT 22.46 DISPLACEMENT PSI _____ MIX PSI _____ RATE 5BPM

REMARKS: Check casing depth w/wireline. Establish rate. Mixt Pump 1 Gal
ESA-41 Flush. Mixt Pump 27 Bbl Telltale dye. Mixt Pump
108 sks 50/50 Por Mix Cement 6% Gel. Follow w/ 45 SKS
OWC Cement. Flush Pump & Lines clean. Displace 4 1/2" Rubber
Plug to casing TD w/ 22.46 BBL ~~Flush~~ water. Formation water
Pressure to 700 PSI. Release pressure to set flow. Check plug depth/wireline.
Mixed cement w/ City water
Customer Supplied Formation water

Fred Maden

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	975 ⁰⁰
5406	65mi	MILEAGE	495	260 ⁰⁰
5402	1415	Casing footage		N/C
5407	312.39	Ton Miles	548	393 ⁶¹
5407	Minimum	Ton Miles	510	330 ⁰⁰
5501C	4 hrs	Transport	505/T106	448 ⁰⁰
1124	10 8 SKS	50/50 Por Mix Cement		1128 ⁶⁰
1126	45 SKS	OWC Cement		805 ⁵⁰
115B	545#	Premium Gel.		109 ⁰⁰
1123	4000 Gal	City Water		62 ⁴⁰
1143	1 Gal	ESA-41		40 ⁴⁰
4404	1	4 1/2" Rubber Plug		45 ⁰⁰

Flavin 3737

AUTHORIZATION [Signature] TITLE pm

SALES TAX 7.2% ESTIMATED TOTAL 4759⁴⁰

DATE 9-2-11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this for