



## Wellbore Schematic

**WELL:** Neely, William G 30-1  
**SSI:** 610010  
**API:** 15-133-26468  
**LOCATION:** NW NE Sec. 30 28S-19E  
**COUNTY:** Neosho  
**STATE:** Kansas

|              |  |
|--------------|--|
| Casing       | 8.625" @ 22'<br>4.5" 10.5# J-55, 4.05" ID w/ 0.0159 bbl/ft capacity @ 1002'  |
| Perforations | Original Perfs: 2/23/06<br>- Summit 465-469' (17)<br>- Mulky 476-480' (17)<br>- Fleming 748-750' (9)<br>- Rowe 932-934' (9)<br>- Neutral 939-940' (5)<br>- Upper Riverton 953-954' (5)<br>- Riverton 991-994' (13)<br>Oil Perfs: 3/27/12<br>- Cattleman 653-664' (22)  |
| Completions  | Spud Date: 2/8/06<br><br>RNUV Completion: 2/23/06<br>- 400 gals 15% HCl<br>- 14 BPM<br>- 9,000# 20/40<br>- 399 bbls fluid<br><br>F Completion: 2/23/06<br>- 500 gals 15% HCl<br>- 18 BPM<br>- 500# 20/40<br>- 154 bbls fluid<br><br>SM Completion: 2/23/06<br>- 400 gals 15% HCl<br>- 13.5 BPM<br>- 8,800# 20/40<br>- 347 bbls fluid<br><br>Cattleman Recompletion: 3/27/12<br>- 17 BPM<br>- 19,000# 20/40, 4,000# 12/20<br>- 368 bbls fluid |

