

Lease:	Schendel	
Owner:	Bobcat Oilfield Services, Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' 6"	Cemented: 5	Hole Size: 8 3/4
Longstring 694.3' 2 7/8 8 rnd	Cemented: 90 sacks	Hole Size: 5 5/8

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: 13-12
Location: SW-SW-SE-NW S24 T16 R21E
County: Miami
FSL: 2805
FEL: 3745
API#: 15-121-29140-00-00
Started: 6/4/12
Completed: 6/5/12

SN: 666'	Packer:
Plugged:	Bottom Plug:

TD: 699'

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	21	589	Shale
3	5	Clay	7	596	Lime
12	17	Lime	2	598	Shale (Oil Sand Streak)
3	20	Shale	14	612	Shale
4	24	Black Shale	4	616	Lime
11	35	Lime	6	622	Black Shale
8	43	Sandy shale	11	633	Lime
19	62	Lime	7	640	Shale
4	66	Shale	5	645	Lime
2	68	Red Bed	6	651	Shale
21	89	Shale	1	652	Lime
15	104	Lime	14	666	Shale (Limey)
8	112	Shale	1	667	Sandy Shale (Oil Sand Streak)
3	115	Sand (Dry)	.5	667.5	Oil Sand (Fair Bleed) (Some Water)
7	122	Shale	1	668.5	Sandy Shale
20	142	Sandy Shale	4.5	673	Oil Sand (Good Bleed) (Very Little Water)
51	193	Shale	1.5	674.5	Oil Sand (Shaley) (Good Bleed)
20	213	Lime	1	675.5	Sandy Shale (Oil Sand Streak)
6	219	Shale	TD	699	Sandy Shale
11	230	Sand (Dry)			
13	243	Shale			
7	250	Lime			
32	282	Shale			
9	3+0	Lime			
4	294	Shale			
1	295	Lime			
17	312	Shale			Surface 6-4-12 Set Time 2:00pm Called 11:00am Becky
26	338	Lime			Longstring 695' 2 7/8 pipe TD 699
9	347	Shale			Set Time 12:00am 6-5-12 Called 11:35am John
21	368	Lime			
4	372	Black Shale			
4	376	Lime			
4	380	Shale			
5	385	Lime			
107	492	Shale			
3	495	Sandy Shale (Oil Sand Streak)			
5	500	Sandy Shale			
52	552	Shale			
10	562	Lime			
5	567	Shale			
1	568	Lime			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 13-12
Location: SW-SW-SE-NW S24 T16 R21E
County: Miami
FSL: 2805
FEL: 3745
API#: 15-121-29140-00-00
Started: 6/4/12
Completed: 6/5/12

Core Run #1

Lease :	Schudel
Owner:	Bobcat Oilfield Services, Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	667	0:00	0	Oil Sand (Fair Bleed) (Some Water)	667.65'
1	668	3:00	3	Sandy Shale	668.55'
2	669	7:30	4.5	Oil Sand (Good Bleed) (Very Little Water)	673'
3	670	10:30	3		
4	671	13:30	3		
5	672	16:30	3		
6	673	20:00	3.5		
7	674	23:30	3.5	Oil Sand (Shaley) (Good Bleed)	674.5'
8	675	28:00	4.5	Sandy Shale (Oil Sand Streaks)	675.5'
9	676	33:00	5	Sandy Shale	
10	677	39:30	6.5		
11	678	46:00	6.5		
12	679	52:00	7		
13	680	59:00	7		
14					
15					
16					
17					
18					
19					
20					

Avery Lumber
P.O. BOX 66
MOUND CITY, KS 66056
{913} 795-2210 FAX {913} 795-2194

Customer Copy

INVOICE

THIS COPY MUST REMAIN AT
MERCHANT AT ALL TIMES!

Page: 1

Invoice: **10041361**

Special :
Instructions :

Time: 13:14:46
Ship Date: 06/05/12
Invoice Date: 06/08/12
Due Date: 07/05/12

Sale rep #: **MAVERY MIKE**

Accl rep code:

REPRINT

Sold To: **BOBCAT OILFIELD SRVC,INC**
C/O BOB EBERHART
30805 COLDWATER RD
LOUISBURG, KS 66053

Ship To: **BOBCAT OILFIELD SRVC,INC**
(913) 837-2823
(913) 837-2823

Customer #: 3570021

Customer PO:

Order By: BOB

poplmg01

5TH

T 27

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

INVOICE

Schendel
13-12 6/15

913-837-4153

Faxed originally 6-8-12

FILLED BY		CHECKED BY	DATE SHIPPED	DRIVER	Sales total		\$4116.80	
SHIP VIA		MIAMI COUNTY			Freight	100.00	Misc + Frgt	100.00
X		RECEIVED COMPLETE AND IN GOOD CONDITION			Taxable	4216.80	Sales tax	318.37
					Non-taxable	0.00		
					Tax #			

TOTAL \$4535.17

1 - Customer Copy

