



**CONSOLIDATED**  
Oil Well Services, LLC

TICKET NUMBER 34828  
LOCATION EUREKA  
FOREMAN KEVIN MCCOY

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**

CEMENT API # 15-015-23948 KS

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-22-12	5631	ARTZ # 1	20	245	4E	Butler
CUSTOMER <u>Noble Petroleum, Inc.</u>			C & G DR19. R19 1			
MAILING ADDRESS <u>3101 N. ROCK Rd Ste 125</u>						
CITY <u>Wichita</u>	STATE <u>Ks</u>	ZIP CODE <u>67226</u>	TRUCK #	DRIVER	TRUCK #	DRIVER
			<u>520</u>	<u>John S.</u>		
			<u>515</u>	<u>Calvin H.</u>		

JOB TYPE SURFACE HOLE SIZE 12 1/4 HOLE DEPTH 229' KB CASING SIZE & WEIGHT 8 5/8 23" NEW  
 CASING DEPTH 218 G.L. DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 15' SLURRY VOL 30 BBL WATER gal/sk 6.5 CEMENT LEFT IN CASING 15'  
 DISPLACEMENT 13.4 BBL DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: SAFETY Meeting: Drilling Rig had some Lost Circulation while Drilling Surface hole. Rig up to 8 5/8 casing. Mixed 125 sks class "A" Cement w/ 3% CAGE 2% GEL 1/4" Flo-Seal /sk @ 15' /gal (Mixed Cotton Seed Hulls w/ Cement to help w/ LC). Displace w/ 13.4 BBL Fresh water. Shut casing in. Good Cement Returns to Surface = 6 BBL Slurry to Pit. Job Complete. Rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	825.00	825.00
5406	25	MILEAGE	4.00	100.00
11045	125 SKS	CLASS "A" Cement	14.95	1868.75
1102	350 *	CAGE 3%	.74 *	259.00
1118 B	235 *	GEL 2%	.21 *	49.35
1107	30 *	Flo-Seal 1/4" /sk	2.35 *	70.50
5407	5.87 TONS	Ton Mileage BULK Delv.	M/c	350.00
			Sub TOTAL	3522.60
		THANK You	SALES TAX 6.55%	147.22
			ESTIMATED TOTAL	3669.82

Revin 3737

AUTHORIZATION Cotton TITLE C & G DR19 Toolpusher DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form