


Lease:	Orest Jones	
Owner:	Bobcat Oilfield Services, Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4
Longstring 466' 2 7/8 8 Rnd	Cemented: 60 sacks	Hole Size: 5 5/8



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 6-12
Location: SW-SW-SW-NE S21T17R25E
County: Miami
FSL: 2805 2823
FEL: 2475
API#: 15-121-29265-00-00
Started: 10/18/12
Completed: 10/19/12

CORRECTED COPY 10/25/12

SN: 437'	Packer:	TD: 475'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil			
11	12	Clay			
42	54	Lime			
2	56	Shale			
1	57	Lime			
47	104	Shale			
10	114	Lime			
13	127	Shale			
5	132	Sandy Shale			
1	133	Coal			
25	158	Shale			
6	164	Lime			
5	169	Black Shale			
6	175	Shale			
8	183	Sandy Shale			
13	196	Shale			
8	204	Lime			
15	219	Shale			
30	249	Lime			
7	256	Black Shale			
21	277	Lime			
4	281	Black Shale			
16	297	Lime			
2	299	Black Shale			
100	399	Shale			
5	404	Sandy Shale (Odor)			
25	429	Shale			Surface 10/18/12 Set Time 5:00pm Called 3:10pm Brooke
1	430	Coal			Longstring 466' 2 7/8" 8 Rnd TD 475'
8	438	Light Shale (Limey)			Set Time 1:30pm Called 1:30pm 10/19/12 Brooke
1	439	Oil Sand (Limey) (Fair Bleed)			
.5	439.5	Lime			
1.5	441	Oil Sand (Good Bleed) (3" Lime Streak at 440)			
2.5	443.5	Oil Sand (Oil & Water) (Fair Bleed)			
.5	444	Oil Sand (Fractured) (Water)			
.5	444.5	Lime			
1.5	446	Oil Sand (Fair Bleed)			
3	449	Lime			
1	450	Oil Sand (Poor Bleed) (Limey)(Water)(Some Shale)			
14	464	Shale			
7	471	Sand (Dry)			
TD	475	Shale			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 6-12
Location: SW-SW-SW-NE S21 T17 R25E
County: Miami
FSL: 285 2823
FEL: 2475
API#: 15-121-29265-00-00
Started: 10/18/12
Completed: 10/19/12

Core Run #1

Lease :	Orest Jones
Owner:	Bobcat Oilfield Services, Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	439	0:00	0	Lime	439.5'
				Oil Sand (Good Bleed)	440.0'
1	440	1:30	1.5	Lime	440.25'
2	441	2:00	.5	Oil Sand (Good Bleed)	441.0'
				Oil Sand (Oil & Water (Fair Bleed)	443.5'
3	442	2:30	.5		
4	443	3:00	.5		
5	444	3:15	.25	Oil Sand (Fractured) (Water)	444.0'
6	445			Locked up Lime	
7	446				
8	447				
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Avery Lumber
P.O. BOX 66
MOUND CITY, KS 66056
{913} 795-2210 FAX {913} 795-2194

Customer Copy
INVOICE

PLEASE REFER TO INVOICE NUMBER
ON ALL CORRESPONDENCE

Page: 1		Invoice: 10044764	
Special :		Time:	15:52:33
Instructions :		Ship Date:	10/15/12
		Invoice Date:	10/16/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	11/05/12
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823	
Customer #: 3570021	Customer PO:	Order By: CLINT	

pop/mgD1 5TH T 28

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

INVOICE

DIRECT DELIVERY
PHONE ORDER BY CLINT
913-837-4157

FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Sales total	\$4116.80
SHIP VIA MIAMI COUNTY				Freight	100.00
RECEIVED COMPLETE AND IN GOOD CONDITION				Taxable	4216.80
X				Non-taxable	0.00
				Sales tax	

TOTAL \$4535.17

2 - Customer Copy

