

JOB LOG

SWIFT Services, Inc.

DATE 11-9-12 PAGE NO. 1

CUSTOMER CHOLLA PRODUCTION WELL NO. 1-29 LEASE BONTRAGER JOB TYPE 5 1/2" 2-STAGE LONGSTRING TICKET NO. 23397

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/HR)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1200							ON LOCATION
	1345							START 5 1/2" CASING IN WELL
								TD-4827 SET = 4825 TP-4831 5 1/2" 15.5 SS-21 CENTRALIZERS-1,3,5,7,9,11,61,95 CMT BSKTS-62,96 DV TOOL = 2244 TOP JT # 62
	1615							DROP BALL - CIRCULATE RECIPROCATE
	1720	6	12		✓	450		PUMP 500 GAL MUDFLUSH
	1722	6	20		✓	450		PUMP 20 BBLs KCL FLUSH
	1730	4 1/4	42		✓	250		MIX CEMENT 175 SKS EA-2 = 15.5 PPG
	1740							WASH OUT PUMP - LINES
	1740							RELEASE 1ST STAGE CATCH DOWN PLUG
	1742	7	0		✓			DISPLACE PLUG
	1800	6	114.5			1500		PLUG DOWN - PSE UP CATCH IN PLUG
	1802							OK RELEASE PSE - HEED
	1805							DROP DV OPENING PLUG
	1820				✓	1100		OPEN DV - CIRCULATE
	1820	6	20		✓	300		PUMP 20 BBLs KCL FLUSH
	1825		7-5					PLUG RH (30SKS) MH (20SKS)
	1835	6	140		✓	150 ^{MG}		MIX CEMENT 250 SKS SMD = 11.2 PPG
	1900							WASH OUT PUMP - LINES
	1900							RELEASE DV CLOSING PLUG
	1902	6 1/2	0		✓			DISPLACE PLUG
	1910	5	53.4			1750		PLUG DOWN - PSE UP CLOSE DV TOOL
	1912							OK RELEASE PSE - HEED
								CIRCULATED 20 SKS CEMENT TO POT
								WASH TRUCK
	2000							JOB COMPLETE <i>Jalyn J. Mondero</i> <i>Wayne</i>
								THANK YOU WAYNE, BLAZNE, DAVE K, FLEET, JEREMY