

**PO Box 884, Chanute, KS 66720**  
**620-431-9210 or 800-467-8676**

TICKET NUMBER 37327  
LOCATION Ottawa, KS  
FOREMAN Casey Kennedy

## FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6/26/12	7069	Reynolds #17	SE5	17	22	M1
CUSTOMER Reusch Oil Well						
MAILING ADDRESS PO Box 520						
CITY Ottawa	STATE KS	ZIP CODE 66067				

TRUCK #	DRIVER	TRUCK #	DRIVER
481	Cashen	CK	
6666	Gar Mao	GM	
548	Mik Haq	MH	
505-Tiole	Jas Ric	JR	

JOB TYPE <u>long string</u>	HOLE SIZE <u>5 7/8"</u>	HOLE DEPTH <u>753'</u>	CASING SIZE & WEIGHT <u>2 7/8" EUE</u>
CASING DEPTH <u>747'</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>2 1/2" rubber plug</u>
DISPLACEMENT <u>4.34 bbls</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE <u>4.6 bph</u>

REMARKS: held safety meeting, established circulation, mixed + pumped 100 # Premium Gel followed by 10 bbls fresh water, mixed + pumped 102 sks 50/50 Pozmix cement w/ 2% gel per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.34 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

0242

[illegible]

Rayin 3737

## AUTHORIZTION

**TITLE**

DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.