



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 37328
LOCATION Ottawa, KS
FOREMAN Casper Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6/28/12	7069	Reynolds # 21	SE 5	17	22	M1
CUSTOMER <u>Reusch Oil Well</u>						
MAILING ADDRESS <u>PO Box 520</u>						
CITY <u>Ottawa</u>		STATE <u>KS</u>	ZIP CODE <u>66067</u>			

TRUCK #	DRIVER	TRUCK #	DRIVER
481	Casper	CK	
1666	Gar Moo	GM	
548	Mik Hag	MH	
505-T106	Jas Ric	JR	

JOB TYPE longstring HOLE SIZE 5 5/8" HOLE DEPTH 764' CASING SIZE & WEIGHT 2 1/8" EUE
 CASING DEPTH 751' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 2 1/2" rubber plug
 DISPLACEMENT 4.37 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4.6 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 100 # Premium Gel followed by 10 bbls fresh water, mixed & pumped 102 sks 50/50 Pozmix cement w/ 2 1/2 gel per sk, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.37 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1030.00
5406	on lease	MILEAGE		
5402	751'	Casing footage		
5407	1/2 minimum	ton mileage		175.00
5501C	1 hr	transport		112.00
1124	102 sks	50/50 Pozmix cement		1116.90
111813	271 #	Premium Gel		56.94
4402	1	2 1/2" rubber plug		28.00
			SALES TAX	90.74
			ESTIMATED TOTAL	2609.55

Ravn 3737

250937

AUTHORIZATION

[Handwritten signature]

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.