



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT
CEMENT**

TICKET NUMBER 34966

LOCATION Ottawa, KS

FOREMAN Casey Kennedy

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10/12/12	7069	Grandon # 25	SW 9	17	22	MI

CUSTOMER Reusch Oil Well		
MAILING ADDRESS 70 Box 520		
CITY Ottawa	STATE KS	ZIP CODE 66606

TRUCK #	DRIVER	TRUCK #	DRIVER
481	Casey	✓ Safety Meeting	
6666	Gar Moo	✓	
510	Set Tuc	✓	
505-7106	Jim Mea	✓	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 700' CASING SIZE & WEIGHT 2 7/8" EUE
CASING DEPTH 692' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT 4.02 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4.5 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 100 # Premium Gel followed by 10 bbls fresh water, mixed & pumped 117 sbs $\frac{50}{50}$ Pozmix cement w/ 2% gel per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.02 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1030.00
5406	on lease	MILEAGE		—
5402	692'	casing footage		—
5407	1/2 minimum	ten mileage		175.00
5501C	1 hr	transport		112.00
1124	117 sbs	$\frac{50}{50}$ Pozmix cement		1281.15
1118B	297 #	Premium Gel		62.37
4402	1	2 1/2" rubber plug		28.00
			SALES TAX	103.55
			ESTIMATED TOTAL	2792.07

Ravin 3737

AUTHORIZATION [Signature] TITLE PRES DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

253696