


Lease:	BURRIS	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4"
Longstring:	Cemented:	Hole Size:
500'FT. OF 2 7/8 8rd	65 SACKS	5 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991


Well #: 21W-12
Location: NE,NE,SW,SW,S12,T17,R24
County: MIAMI
FSL:1007
FEL: 4187
API#: 15-121-29412-00-00
Started: 1/16/13
Completed: 1/17/13

SN: NONE	Packer: NONE
Plugged:	Bottom Plug:

TD: 505' FT.

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil			
5	6	Clay			
38	44	Lime			
1	45	Clay			
1	46	Lime			
50	96	Shale			
10	106	Lime			
27	133	Shale			
5	138	Lime			
48	186	Shale			
9	195	Lime			
15	210	Shale			
29	239	Lime			
6	245	Black Shale			
4	249	Lime (Shaley)			
18	267	Lime			
3	270	Black shale			
2	272	Lime			
3	275	Shale			SET SURFACE 1/16/13
7	282	Lime			SET TIME 12:30 P.M.
4	286	Shale			CALLED IN 10:30 A.M. TALKED TO JUDY
2	288	Shale (Limey)			WELL TD 505' FT.
3	291	Sandy Shale (Oil Sand Streak)			LONG STRING 500'FT. OF 2 7/8" 8RD PIPE
30	321	Shale			SET TIME 4:00 P.M. 1/17/13
12	333	Sandy Shale			CALLED IN 3:00 P.M. TALKED TO BROOKE
60	393	Shale			
8	401	Sandy Shale (Odor)			
25	426	Shale			
1	427	Black Shale			
27	454	Shale			
10.5	464.5	Oil Sand (Some Shale) (Fair Bleed) (lime Streak) (Oil & Water)			
3.5	468	Oil Sand (Oil & Water) (Shaley)			
1.5	469.5	Oil Sand (Fair Bleed)			
.5	470	Lime			
3	473	Oil Sand (Oil & Some Water) (Good Bleed)			
10	483	Shale			
5	488	Lime			
4	492	Shale			
8	500	Lime (Shaley)			
3	503	Shale			
TD	505	Lime			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 21W-12
Location: NE,SW,SW,SW,S12,T17,R24
County: MIAMI
FSL: 1007
FEL: 4187
API#: 15-121-29412-00-00
Started: 1/16/13
Completed: 1/17/13

Core Run #1

Lease :	BURRIS
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	456	0:00	-----		
1	457	1:30	1.5		
2	458	3:00	1.5		
3	459	4:00	1		
4	460	5:00	1		
5	461	6:00	1	OIL SAND (OIL & WATER) (SOME SHALE) (FAIR BLEED)	464.5'
6	462	7:30	1.5		
7	463	9:00	1.5		
8	464	10:00	1		
9	465	11:30	1.5		
10	466	13:00	1.5	OIL SAND (OIL & WATER) (SHALEY)	468'
11	467	14:00	1		
12	468	15:30	1.5		
13	469	16:00	.5	OIL SAND (FAIR BLEED)	469.5'
14	470	17:30	1.5	LIME	470'
15	471	18:30	1		
16	472	19:00	.5	OIL SAND (OIL & SOME WATER) (GOOD BLEED)	473'
17	473	20:00	1		
18	474	22:30	2.5		
19	475	25:30	3	SHALE	
20	476	27:30	2		

Jan. 11. 2013 8:30AM

Avery Lumber 913-795-2194,
Avery Lumber
P.O. BOX 66
MOUND CITY, KS 66056
(913) 795-2210 FAX (913) 795-2194

No. 4022 P. 1

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER
ON ALL CORRESPONDENCE

Page: 1

Invoice: **10046461**

Special :	Time: 11:16:09
Instructions :	Ship Date: 01/07/13
	Invoice Date: 01/11/13
Sale rep #: MAVERY MIKE	Acct rep code:
	Due Date: 02/05/13

Sold To: **BOBCAT OILFIELD SRVC, INC**
C/O BOB EBERHART
30805 COLDWATER RD
LOUISBURG, KS 66053

Ship To: **BOBCAT OILFIELD SRVC, INC**
(913) 837-2823
(913) 837-2823

Customer #: 3570021

Customer PO:

Order By: CLINT

peping01

5TH
T 28

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
380.00	380.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	3378.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

*Burris
2/11/12*

*PHONE ORDER BY CLIENT
DIRECT DELIVERY*

INVOICE

913-837-4154

FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____ SHIP VIA MIAMI COUNTY RECEIVED COMPLETE AND IN GOOD CONDITION X	Freight	100.00	Sales total	\$5005.80
	Taxable	5105.80	Misc + Frgt	100.00
	Non-taxable	0.00	Sales tax	385.49
Tax #				

TOTAL \$5491.29

2 - Customer Copy

