

Lease:	Rigney	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 498' Ft. Of 2 7/8" 8rd	Cemented: 62 Sacks	Hole Size: 5 5/8"

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: 4W-12
Location: NE SE NW SW S12 T17 R24E
County: Miami
FSL: 1668
FEL: 4192
API#: 15-121-29391-00-00
Started: 12-24-12
Completed: 12-28-12

SN: NONE	Packer: NONE	TD: 501'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	3	493	Lime
5	6	Clay	4	497	Shale
34	40	Lime	TD	501	Lime (Odor)
49	89	Shale			
9	98	Lime			
6	104	Shale			
8	112	Sandy Shale			
3	115	Sand (Oil Show) (Shaley)			
2	117	Shale (Coal Streak)			
11	128	Shale			
5	133	Lime			
25	158	Shale			
6	164	Sandy Shale (Oil Show)			
14	178	Shale			
9	187	Lime			Surface 12-24-12
14	201	Shale			Set Time 4:00 PM
30	231	Lime			Called 12-26-12 – Talked To Brooke
6	237	Black Shale			Well TD – 501' Ft.
19	256	Lime			
4	260	Black Shale			Long string 498' Ft. Of 2 7/8" 8rd Pipe
5	265	Lime			Set Time 12:00 PM On 12-28-12
4	269	Shale			Called 10:45 AM On 12-28-12 – Talked To Brooke
5	274	Lime			
3	277	Shale			
3	280	Shale (Limey)			
6	286	Sandy Shale			
18	304	Shale			
20	324	Sand (Dry) (Shaley)			
96	420	Shale			
1	421	Black Shale			
28	449	Shale			
.5	449.5	Lime			
.5	450	Oil Sand (Shaley) (Water)			
1.5	451.5	Oil Sand (Limey) (Water)			
12.5	464	Oil Sand (Water) (Very Little Oil)			
5	469	Oil Sand (Oil & Some Water) (Fair Bleed)			
8	477	Shale			
6	483	Lime			
2	485	Black Shale			
2	487	Lime			
3	490	Shale			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4W-12
Location: NE SE NW SW S12 T17 R24 E
County: Miami
FSL: 1668
FEL: 4192
API#: 15-121-29391-00-00
Started: 12-24-12
Completed: 12-28-12

Lease :	Rigney
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	450	0:00	0	Oil Sand (Limey) (Water)	451.5'
1	451	1:30	1.5		
2	452	3:00	1.5	Oil Sand (Water) (Very Little Oil) (Some Shale)	464'
3	453	4:00	1		
4	454	4:3	.5		
5	455	5:30	1		
6	456	7:00	1.5		
7	457	8:00	1		
8	458	9:30	1.5		
9	459	11:00	1.5		
10	460	12:30	1.5		
11	461	14:00	1.5		
12	462	16:00	2		
13	463	18:00	2		
		21:30			
14	464	23:00	1.5		
15	465	24:30	1.5	Oil Sand (Oil & Some Water) (Fair Bleed)	469'
16	466	25:30	1		
17	467	26:30	1		
18	468	28:00	1.5		
19	469	29:30	1.5		
20	470	32:00	2.5	Shale	

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER ON ALL CORRESPONDENCE

Page: 1		Invoice: 10046133	
Special :		Time:	13:37:55
Instructions :		Ship Date:	12/17/12
		Invoice Date:	12/17/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	01/05/13
Sold To: BOBCAT OILFIELD SRVC, INC		Ship To: BOBCAT OILFIELD SRVC, INC	
C/O BOB EBERHART		(913) 837-2823	
30805 COLDWATER RD		(913) 837-2823	
LOUISBURG, KS 66053			
Customer #: 3570021	Customer PO:	Order By:	

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

*Rigney
4W-12*

*Phone order by Bob
Direct Delivery*

INVOICE

913 837 4159

<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>FILLED BY</td> <td>CHECKED BY</td> <td>DATE SHIPPED</td> <td>DRIVER</td> </tr> <tr> <td colspan="4">SHIP VIA MIAMI COUNTY</td> </tr> <tr> <td colspan="4" style="text-align: center;">RECEIVED COMPLETE AND IN GOOD CONDITION</td> </tr> <tr> <td colspan="4" style="text-align: center;">X</td> </tr> </table>	FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	SHIP VIA MIAMI COUNTY				RECEIVED COMPLETE AND IN GOOD CONDITION				X				<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>Sales total</td> <td style="text-align: right;">\$4116.80</td> </tr> <tr> <td>Freight</td> <td style="text-align: right;">100.00</td> </tr> <tr> <td>Misc + Frgt</td> <td style="text-align: right;">100.00</td> </tr> <tr> <td>Taxable</td> <td style="text-align: right;">4216.80</td> </tr> <tr> <td>Non-taxable</td> <td style="text-align: right;">0.00</td> </tr> <tr> <td>Sales tax</td> <td style="text-align: right;">318.37</td> </tr> <tr> <td>Tax #</td> <td></td> </tr> </table>	Sales total	\$4116.80	Freight	100.00	Misc + Frgt	100.00	Taxable	4216.80	Non-taxable	0.00	Sales tax	318.37	Tax #	
FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER																												
SHIP VIA MIAMI COUNTY																															
RECEIVED COMPLETE AND IN GOOD CONDITION																															
X																															
Sales total	\$4116.80																														
Freight	100.00																														
Misc + Frgt	100.00																														
Taxable	4216.80																														
Non-taxable	0.00																														
Sales tax	318.37																														
Tax #																															

TOTAL \$4535.17

2 - Customer Copy

