


Lease:	Rigney	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4"
Longstring:	Cemented:	Hole Size:
499'Ft. Of 2 7/8" 8rd	62 Sacks	5 5/8"



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991



Well #: 5W-12
Location: NW SW NE SW S12 T17R24E
County: Miami
FSL: 1670
FEL: 3855
API#: 15-121-29392-00-00
Started: 12-21-12
Completed: 12-24-12

SN: NONE	Packer: NONE
Plugged:	Bottom Plug:

TD: 505'

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil			
6	7	Clay			
45	52	Lime			
49	101	Shale			
10	111	Lime			
8	119	Shale			
7	126	Gas Sand (Odor)			
2	128	Shale (Coal Streak)			
11	139	Shale			
6	145	Lime			
24	169	Shale			
4	173	Shale (Oil Sand Streak)			
6	179	Shale			
2	181	Sandy Shale (Odor)			
10	191	Shale			Surface 12-21-12
4	200	Lime			Set Time 4:00 PM
14	214	Shale			Called 2:00 PM On 12-21-12 – Talked To Brooke
29	243	Lime			Well TD – 505' Ft.
5	248	Black Shale			
21	269	Lime			Long string 499' Ft. Of 2 7/8" 8rd Pipe
4	273	Black Shale			Set Time 3:00 PM On 12-24-12
2	275	Lime			Called 8:15 AM On 12-26-12 – Talked To Brooke
6	281	Shale			
5	286	Lime			
5	291	Shale			
17	308	Sandy Shale			
31	339	Sand (Slight Odor)			
95	434	Shale			
1	435	Black Shale			
17	452	Shale			
4	456	Sandy Shale (Odor)			
3	459	Oil Sand (Very Shaley) (Fair Bleed)			
2	461	Sandy Shale (Oil Sand Streak)			
3	464	Sandy Shale			
3	467	Oil Sand (Shaley) (Fair Bleed) (Oil Water)			
11	478	Oil Sand (Some Shale) (Water Some Oil)			
5	483	Oil Sand (Some Shale) (Fair Bleed) (Oil & Some Water)			
.5	483.5	Gas Sand			
7.5	491	Shale			
5	496	Lime			
TD	505	Shale (Limey)			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Core Run #1

Lease :	Rigney
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Well #: 5W-12
Location: NW SW NE SW S12 T17 R24 E
County: Miami
FSL: 1670
FEL: 3855
API#: 15-121-29392-00-00
Started: 12-21-12
Completed: 12-24-12

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	467	0:00	0	Oil Sand (Some Shale) (Water & Some Show Of Oil)	478'
1	468	1:00	1		
2	469	2:00	1		
3	470	3:00	1		
4	471	4:00	1		
5	472	5:00	1		
6	473	6:00	1		
7	474	7:00	1		
8	475	8:00	1		
9	476	9:00	1		
10	477	10:00	1		
11	478	11:00	1	Oil Sand (Some Shale) (Fair Bleed) (Oil & Some Water)	483'
12	479	12:00	1		
13	480	12:30	.5		
14	481	13:30	1		
15	482	14:00	.5		
16	483	15:00	1		
17	484	16:3	1.5	Gas sand Shale	483.5'
18	485	18:30	2		
19	486	20:30	2		
20	487	22:00	1.5		

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER
 ON ALL CORRESPONDENCE

Page: 1

Invoice: **10046133**

Special :	Time: 13:37:55
Instructions :	Ship Date: 12/17/12
	Invoice Date: 12/17/12
Sale rep #: MAVERY MIKE	Due Date: 01/05/13
Acct rep code:	

Sold To: BOBCAT OILFIELD SRVC, INC	Ship To: BOBCAT OILFIELD SRVC, INC
C/O BOB EBERHART	(913) 837-2823
30805 COLDWATER RD	
LOUISBURG, KS 66053	(913) 837-2823

Customer #: 3570021 Customer PO: Order By:

popimg01

5TH
T 26

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

*Rigney
5W-12*

*Phone order by Bob
Direct Delivery*

INVOICE

913 837 4159

X	FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Sales total	\$4116.80	
	SHIP VIA MIAMI COUNTY				Freight	100.00	
	RECEIVED COMPLETE AND IN GOOD CONDITION				Taxable	4216.80	
				Non-taxable	0.00	Misc + Frgt	100.00
				Tax #		Sales tax	318.37

TOTAL \$4535.17

2 - Customer Copy



* 0 0 1 M P T 0 0 1 0 J A H D 1 I *