

Formation Tops

Formation	King Oil II, LLC. Querbach #4-10 Sec. 10 T23s R22w 1290' FNL & 342' FWL
Anhydrite	1327', +881
Base	1361', +847
Heebner	3763', -1555
Lansing	3828', -1620
Stark	4084', -1876
BKc	4186', -1978
Marmaton	4204', -1996
Pawnee	4271', -2063
Fort Scott	4356', -2148
Cherokee	4382', -2174
Mississippian	4425', -2217
Osage	4445', -2237
RTD	4453', -2245

Sample Zone Descriptions

Miss. Osage

(4445', -2237): Covered in DST #1

Δ – White to Clear, mostly fresh, slightly triptolic with pinpoint vuggy porosity, light spotted oil stain in porosity, slight show of free oil, very light odor, light spotted yellow fluorescents, 8 units hotwire.