

ALLIED CEMENTING CO., LLC. 040693

Federal Tax I.D.# 20-5975804

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge KS.

DATE <u>2-20-2011</u>	SEC. <u>14</u>	TWP. <u>35 S</u>	RANGE <u>13 W</u>	CALLED OUT <u>12:30 PM</u>	ON LOCATION <u>1:15 PM</u>	JOB START <u>5:10 PM</u>	JOB FINISH <u>6:00 PM</u>
LEASE <u>Myers</u>	WELL # <u>1</u>	LOCATION <u>Hardner, KS. Zwest</u>			COUNTY <u>Barber</u>	STATE <u>KS.</u>	
OLD OR NEW (Circle one)		<u>1/2 south w/s</u>					

CONTRACTOR H-2 Drilling
 TYPE OF JOB Production
 HOLE SIZE 7 7/8 T.D. 5600+
 CASING SIZE 5 1/2 x 15.8 DEPTH WEEL FILE
 TUBING SIZE WEEL FILE DEPTH WEEL FILE
 DRILL PIPE Regulator DEPTH WEEL FILE
 TOOL Drig & Core DEPTH WEEL FILE
 PRES. MAX 1500 Tests / Meters WEEL FILE
 MEAS. LINE WEEL FILE SHOE JOINT 41.27
 CEMENT LEFT IN CSG. WEEL FILE
 PERFS. WEEL FILE
 DISPLACEMENT 127 1/2 Bbls 2% KCL water

OWNER Woolsey Operating
 CEMENT
 AMOUNT ORDERED 75 sx 60:40:4% GEL
150 sx Class H + 10% Gypseal 10% salt 6"
Kolseal - 8% FI-160 + 1/4" floseal 13 Gals Clapro
 COMMON A 45 sx @ 15.45 695.25
 POZMIX 30 sx @ 8.00 240.00
 GEL 3 sx @ 20.80 62.40
 CHLORIDE @
 ASC @
H 150 sx @ 16.80 2520.00
Gypseal 14 sx @ 29.20 408.80
Salt 16 sx @ 12.00 192.00
Kolseal 900 # @ .89 801.00
FI-160 113 # @ 13.30 1502.90
Floseal 37.5 # @ 2.50 93.75
Clapro 13 Gals @ 3.25 406.25
 HANDLING 280 @ 2.40 672.00
 MILEAGE 280 / .10 / 25 700.00
 TOTAL 8294.35

EQUIPMENT
 PUMP TRUCK CEMENTER Carl Balding / Matt Thimesch
 #471-265 HELPER Tason Thimesch
 BULK TRUCK # 364 DRIVER Raymond Romans
 BULK TRUCK # DRIVER

REMARKS:

Run 5251' 5 1/2 casing, Drop ball + circulate on bottom for 1 hour, Mix 25 sx 60:40:4% GEL for Rat Hole, mix 50 sx 60:40:4 scavenger slurry mix + pump 150 sx Class H + Additives wash pump + lines + Release plug. Displace with 127 1/2 Bbl 2% KCL water. ~~Release~~ Bump plug, Release pressure + float Hold (Thank you)

SERVICE

DEPTH OF JOB 5251'
 PUMP TRUCK CHARGE 2185.00
 EXTRA FOOTAGE @
 MILEAGE 25 @ 7.00 175.00
 MANIFOLD @
 TOTAL 2360.00

CHARGE TO: Woolsey Operating
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

1- AFU float shoe @ 214.20
1- Latch Down plug @ 163.80
10- Turbolizers @ 40.60 406.00
24- Recip scratchers @ 23.94 574.56
1- Basket @ 161.00
 TOTAL 1519.56

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____
 TOTAL CHARGES (Signature)
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME MIKE THARP
 SIGNATURE (Signature)

ALLIED CEMENTING CO., LLC. 040645

Federal Tax I.D.# 20-5975804

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Madeline Lodgett

DATE <i>2-8-11</i>	SEC. <i>14</i>	TWP. <i>35s</i>	RANGE <i>13w</i>	CALLED OUT	ON LOCATION	JOB START <i>4:00am</i>	JOB FINISH <i>5:00am</i>
LEASE <i>Myers</i>	WELL # <i>1</i>	LOCATION <i>2 W of Hardner 1/2 S W intg</i>			COUNTY <i>Barber</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)							

CONTRACTOR *H-2 O-Ming*
 TYPE OF JOB *Surface*
 HOLE SIZE *14 3/4* T.D. *254'*
 CASING SIZE *10 3/4* DEPTH *251'*
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX *406 psi* MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG. *20'*
 PERFS.
 DISPLACEMENT *22 1/2 bbls H2O*

EQUIPMENT
 PUMP TRUCK CEMENTER *Matt Thinesch*
 # *471/265* HELPER *Sason Thinesch*
 BULK TRUCK
 # *356/252* DRIVER *Raymond R.*
 BULK TRUCK
 # DRIVER

REMARKS:
*Back circulation with RTG
 pump 3 bbls H2O ahead
 mix 240 sk cement Displace 22 1/2 bbls H2O
 SHUT IN. cement did circulate*

CHARGE TO: *Woolsey Operating*
 STREET
 CITY STATE ZIP

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *MIKE THARP*
 SIGNATURE *[Signature]*

OWNER *Woolsey operating*

CEMENT
 AMOUNT ORDERED *240 sk class A + 3% coat 2% set*

COMMON *A 240 SK @ 15 45 3708 00*
 POZMIX @
 GEL *5 SK @ 20 80 104 00*
 CHLORIDE *9 SK @ 58 20 523 00*
 ASC **WELL FILE** @
 Regulatory Correspondence @
 Drilling Comp Workovers @
 Tests / Meters Operations @
 @
 @
 @
 @
 HANDLING *254 @ 2 40 609 60*
 MILEAGE *254/-10/20 508 00*
 TOTAL *5453 40*

SERVICE
 DEPTH OF JOB *251'*
 PUMP TRUCK CHARGE *1018 00*
 EXTRA FOOTAGE @
 MILEAGE *20 @ 7 140 00*
 MANIFOLD @
 @
 @
 TOTAL *1158 00*

PLUG & FLOAT EQUIPMENT
 @
 @
 @
 @
 @
 TOTAL

SALES TAX (If Any)
 TOTAL CHARGES *[Crossed out]*
 DISCOUNT *[Crossed out]* IF PAID IN 30 DAYS
[Crossed out]