

Lease:	Burris	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4
Longstring: 504' 2 7/8rd	Cemented: 60	Hole Size: 5 5/8


Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 1W-12
Location: SW SE SW SW S12 T17R24E
County: Miami
FSL: 60
FEL: 4370
API#: 15-121-29368-00-00
Started: 11-28-12
Completed: 11-29-12

SN: NONE	Packer:	TD: 510'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	5	504	Shale
7	8	Clay	TD	510	Lime(Oil show)
31	39	Lime			
57	90	Shale			
11	101	Lime			
15	126	Shale			
5	131	Lime			
49	180	Shale			
8	188	Lime			
15	203	Shale			
28	231	Lime			
3	234	Black Shale			
4	238	Light Shale			
7	245	Shale(Limey)			
14	259	Lime			Surface 11-28-12
5	264	Black Shale			Set Time 12:00 PM
2	266	Lime			Called 11:05 AM Brooke
5	271	Shale			
5	276	Lime			
5	281	Shale(Limey)			Longstring 504' 2 7/8" 8rd TD 510'
3	284	Sandy Shale(oil sand stk)			Set Time 4:30 PM 11-29-12
14	298	Shale			Called 3:20 PM Brooke
23	321	Sand(dry)(taking fluid)			
100	421	Shale			
2	423	Black Shale			
31	454	Shale			
2	456	Shaley(Limey)			
2	458	Shale(oil sand stk)(oil show)			
3	461	Oil sand Shaley(Fair Bleed)			
3	464	Oil sand(water)(some oil)			
2.5	466.5	Oil sand limey(oil &water) Fair Bleed			
0.5	467	Lime			
1	468	Oil sand("water") (some oil) (Poor Bleed)			
2.5	470.5	Oil sand (oil &water) (Fair Bleed)			
2	472.5	Oil sand (water)(some oil)(Poor Bleed)			
1.5	474	Oil sand (oil &water)(Fair Bleed)			
10	484	Shale			
4	488	Lime			
3	491	Shale			
7	498	Lime(Shaley)			
1	499	Coal			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 1W-12
Location: SW SE SW SW S12 T17 R24 E
County: Miami
FSL: 60
FEL: 4370
API#: 15-121-29368-00-00
Started: 11-28-12
Completed: 11-29-12

Core Run #1

Lease :	Burris
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	460				
1	461		1	Oil sand (shaley) Fair Bleed	461
2	462		1		
3	463		1/2	Oil sand "water" & (some oil)	464
4	464		1		
5	465		1	Oil sand Limey (oil & water/ Fair Bleed)	466 1/2
6	466		1/2		
7	467		1 1/2	Lime	467
8	468		1/2	Oil sand ("water/some oil poor bleed)	468
9	469		1/2		
10	470		1/2	Oil sand (oil &water/ Fair Bleed)	470 1/2
11	471		1/2	Oil sand (water) (some oil/ Poor Bleed)	472 1/2
12	472		1/2		
13	473		1	Oil sand (oil &water/ Fair Bleed)	474
14	474		1/2		
15	475		2 1/2		
16	476		2 1/2		
17	477		2 1/2	Shale	
18	478		2 1/2		
19					
20					

Avery Lumber
P.O. BOX 66
MOUND CITY, KS 66056
(913) 795-2210 FAX (913) 795-2194

Customer Copy
INVOICE

PLEASE REFER TO INVOICE NUMBER
ON ALL CORRESPONDENCE

Page: 1		Invoice: 10045770	
Special :		Time:	14:54:09
Instructions :		Ship Date:	11/28/12
		Invoice Date:	11/30/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	01/05/13
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823	
Customer #: 3570021	Customer PO:	Order By: BOB	

popimg01

STH
T 27

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

NOTE

OK RE

DIRECT DELIVERY
PHONE ORDER BY BOB

913-837-4159

X	FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Freight	100.00	Sales total	\$4116.80
	SHIP VIA MIAMI COUNTY				Taxable	4216.80	Misc + Frgt	100.00
	RECEIVED COMPLETE AND IN GOOD CONDITION				Non-taxable	0.00	Sales tax	318.37
					Tax #			

TOTAL \$4535.17

2 - Customer Copy



* 0 0 1 M E 0 0 0 1 0 T E P J 4 K *