


Lease:	Burris	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 517' Ft. Of 2 7/8 8rd	Cemented: 62 Sacks	Hole Size: 5 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 2W-12
Location: SE SE SW SW S12 T17 R24E
County: Miami
FSL: 60
FEL: 4035
API#: 15-121-29369-00-00
Started: 11-29-12
Completed: 12-03-12

SN: NONE	Packer: NONE	TD: 521' Ft
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	2.5	491.5	Oil Sand (Fair Bleed) (Slight Show Of Water)
7	8	Clay	.5	492	Gas Sand
43	51	Lime (Clay Streak) (Taking Fluid)	10	502	Shale
50	101	Shale	4	506	Lime
10	111	Lime	TD	521	Shale Limey
18	139	Shale			
5	144	Lime			
50	194	Shale			
8	202	Lime			
15	217	Shale			
28	245	Lime			
6	251	Black Shale			
6	257	Shale			
17	274	Lime			
4	278	Black Shale			Surface 11-29-12
2	280	Lime			Set Time 5:30 PM
6	286	Shale			Called 3:20 PM – Talked To Brooke
5	291	Lime			
3	294	Shale			Well TD 521'
6	300	Sandy Shale (Oil Show)			Longstring 517' 2 7/8" 8rd Pipe
11	311	Shale			Set Time 4:30 PM 12-03-12
23	334	Gas Sand (Slight Oil Show)			Called 3:15 PM – Talked To Brooke
701	404	Shale			
4	408	Sandy Shale (Oil Show)			
3	411	Oil Sand (Shaley) (Fair Bleed)			
3	414	Sandy Shale (Oil Show)			
3	417	Sandy Shale (Odor)			
19	436	Shale			
2	438	Black Shale			
32	470	Shale			
2	472	Shale (Limey)			
3.5	475.5	Oil Sand (Shaley) (Fair Bleed)			
2	477.5	Oil Sand (Some Shale) (Oil & Water) (Fair Bleed)			
2	479.5	Oil Sand (Water/Some Oil) (Some Shale) (Poor Bleed)			
.5	480	Lime			
.5	480.5	Oil Sand ("Water")			
.5	481	Lime			
2	483	Oil Sand (Oil & Water) (Fair Bleed)			
2	485	Sand (Dry) (Limey)			
1	486	Oil Sand (Oil & Water) (Fair Bleed)			
3	489	Oil Sand (Good Bleed) (Slight Show Of Water)			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 2W-12
Location: SE SE SW SW S12 T17 R24 E
County: Miami
FSL: 60
FEL: 4035
API#: 15-121-29369-00-00
Started: 11-29-12
Completed: 12-03-12

Core Run #1

Lease :	Burris
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	474	0:00	0	Oil Sand (Shaley) (Fair Bleed)	475.5'
1	475	1:30	1.5		
2	476	2:30	1	Oil Sand (Some Shale) (Oil & Water) (Fair Bleed)	477.5'
3	477	3:30	1		
4	478	4:00	.5	Oil Sand (Some Shale) (Water & Oil) (Poor Bleed)	479.5'
5	479	5:00	1		
6	480	6:30	1.5	Lime	480'
				Oil Sand ("Water")	480.5'
7	481	7:30	1	Lime	481'
				Oil Sand (Oil & Water) Fair Bleed)	483'
8	482	8:00	.5		
9	483	9:00	1		
				Sand (Dry) (Limey)	485'
10	484	10:00	1		
11	485	11:00	1		
				Oil Sand (Oil & Water) (Fair Bleed)	486'
12	486	12:00	1		
				Oil Sand (Good Bleed) (Slight Show Of Water)	489'
13	487	13:00	1		
14	488	14:00	1		
15	489	15:00	1		
				Oil Sand (Fair Bleed) (Slight Show Of Water)	491.5'
16	490	15:30	.5		
17	491	16:00	.5		
18	492	17:00	1	Gas Sand	492'
19	493	20:30	3.5	Shale	
20	494	24:30	4		

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy
INVOICE

PLEASE REFER TO INVOICE NUMBER
 ON ALL CORRESPONDENCE

Page: 1		Invoice: 10045770	
Special :		Time:	14:54:09
Instructions :		Ship Date:	11/28/12
		Invoice Date:	11/30/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	01/05/13
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823	
Customer #: 3570021	Customer PO:	Order By: BOB	

paping01

5TH
T 27

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

INVOICE

OK RE
Burr's
2/12

DIRECT DELIVERY
PHONE ORDER BY BOB

913-837-4159

FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Sales total	\$4116.80
SHIP VIA MIAMI COUNTY				Freight	100.00
RECEIVED COMPLETE AND IN GOOD CONDITION				Taxable	4216.80
X				Non-taxable	0.00
				Sales tax	

TOTAL \$4535.17

2 - Customer Copy

