

Lease:	Burris	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 508' 2 7/8 8rd Pipe	Cemented: 62	Hole Size: 5 5/8"

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: 4W-12
Location: SE SW SE SW S12 T17 R24E
County: Miami
FSL: 60
FEL: 3368
API#: 15-121-29371-00-00
Started: 12-03-12
Completed: 12-04-12

SN: NONE	Packer: NONE	TD: 515' Ft.
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	4	512	Shale
4	5	Clay	TD	515	Lime
42	47	Lime			
49	96	Shale			
9	105	Lime			
6	111	Shale			
11	122	Black Sand (Oil Show)			
15	137	Shale			
5	142	Lime			
49	191	Shale			
7	198	Lime			
15	213	Shale			
29	242	Lime			
6	248	Black Shale			
4	252	Shale (Limey)			Surface 12-03-12
19	271	Lime			Set Time 5:30 PM
4	275	Black Shale			Called 3:15 PM – Talked To Brooke
2	277	Lime			
6	283	Shale			Well TD 515' Ft.
5	288	Lime			Long string 508' 2 7/8" 8rd Pipe
3	291	Shale			Set Time 4:30 PM 12-04-12
4	295	Shale (Limey)			Called 3:30 PM – Talked To Brooke
3	298	Oil Sand (Very Shaley) (Fair Bleed)			
13	311	Shale			
5	316	Sandy Shale			
5	321	Shale			
15	336	Sandy Shale			
89	425	Shale			
1	426	Black Shale			
37	463	Shale			
1	464	Shale (Limey)			
6	470	Shale (Oil Sand Streak)			
1.5	471.5	Oil Sand (Shaley) (Fair Bleed)			
2	473.5	Oil Sand (Fair Bleed) (Black)			
1.5	475	Oil Sand (Water & Some Oil) (Poor Bleed)			
5.5	480.5	Oil Sand (Fair Bleed) (Black)			
1.5	482	Sand (Dy) (Limey)			
1	483	Sand (Dry)			
12	495	Shale			
2	497	Lime			
11	508	Shale (Limey)			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4W-12
Location: SE SW SE SW S12 T17 R24 E
County: Miami
FSL: 60
FEL: 3368
API#: 15-121-29371-00-00
Started: 12-03-12
Completed: 12-04-12

Core Run #1

Lease :	Burris
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	466	0:00	0	Sandy Shale (Some Oil Sand Streak)	466'
1	467	2:00	2		
2	468	3:30	1.5		
3	469	5:30	2		
4	470	7:30	2	Oil Sand Shaley (Fair bleed)	470'
5	471	9:00	1.5		471.5'
6	472	10:30	1.5	Oil Sand (Fair Bleed) (Black)	473.5'
7	473	1:30	1		
8	474	12:30	1	Oil Sand (Water & Some Oil) (Poor Bleed) (Black)	475'
9	475	13:30	1		
10	476	14:00	.5		
11	477	15:00	1	Oil Sand (Fair Bleed) (Black)	480.5'
12	478	16:00	1		
13	479	17:30	1.5		
14	480	18:30	1		
15	481	20:00	.5	Sand (Dry) (Limey)	482'
16	482	21:00	1		
17	483	22:30	.5		
18					
19					
20					

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER
 ON ALL CORRESPONDENCE

Page: 1		Invoice: 10045770	
Special :		Time:	14:54:09
Instructions :		Ship Date:	11/28/12
		Invoice Date:	11/30/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	01/05/13
Sold To: BOBCAT OILFIELD SRVC, INC		Ship To: BOBCAT OILFIELD SRVC, INC	
C/O BOB EBERHART		(913) 837-2823	
30805 COLDWATER RD			
LOUISBURG, KS 66053		(913) 837-2823	
Customer #: 3570021	Customer PO:	Order By: BOB	

paping01

5TH
T 27

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

INVOICE

OK RE
Burnis
4W-12

DIRECT DELIVERY
PHONE ORDER BY BOB

913-837-4159

FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Sales total	\$4116.80
SHIP VIA MIAMI COUNTY				Freight	100.00
RECEIVED COMPLETE AND IN GOOD CONDITION				Taxable	4216.80
X				Non-taxable	0.00
				Sales tax	318.37
				Tax #	

TOTAL \$4535.17

2 - Customer Copy

