

Lease:	Burriss	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4"
Longstring:	Cemented:	Hole Size:
466'Ft Of 2 7/8" 8rd	62 Sacks	5 5/8"

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: 8W-12
Location: NE NW SW SW S12 T17 R24E
County: Miami
FSL: 1310
FEL: 4855
API#: 15-121-29375-00-00
Started: 12-18-12
Completed: 12-19-12

SN: NONE	Packer: NONE	TD: 470' Ft.
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	7	457	Lime (Shale Streaks)
5	6	Clay	12	469	Shale
16	16	Lime	TD	470	Lime
49	65	Shale			
10	75	Lime			
25	100	Shale			
5	105	Lime			
25	130	Shale			
7	137	Sandy Shale (Slight Oil Shale)			
14	151	Shale			
10	161	Lime			
14	175	Shale			
29	204	Lime			
5	209	Black Shale			
22	231	Lime			Surface 12-18-12
3	234	Black Shale			Set Time 4:00 PM
2	236	Lime			Called 1:45 PM – Talked To Brooke
6	242	Shale			Well TD – 470' Ft.
6	248	Lime			
3	251	Shale			Long string 466' Ft. Of 2 7/8" 8rd Pipe
5	256	Sandy Shale			Set Time 2:30 PM - 12-19-12
30	286	Shale			Called in 1:30 PM – Talked To Brooke
20	306	Sand (Dry) (Shaley)			
52	358	Shale			
3	364	Shale (Limey)			
6	367	Sandy Shale (Oil Sand Streak) (Fair Bleed)			
25	392	Shale			
1	393	Black Shale			
30	423	Shale			
1	424	Oil Sand (Shaley)(Limey)(Fair Bleed)(Some Water)			
2.5	426.5	Oil Sand ("Water")			
1.5	428	Oil Sand (Oil & Water) (Fair Bleed)			
2	430	Oil Sand ("Water")			
1	431	Oil Sand (Fractured) ("Water")			
2.5	433.5	Oil Sand ("Water")			
1.5	435	Oil Sand (Oil & Water) Fair Bleed)			
1	436	Oil Sand ("Water")			
1	437	Oil Sand (Limey) (Good Bleed)			
1.5	438.5	Oil Sand (Some Shale) (Fair Bleed) (Some Water)			
2	440.5	Oil Sand (Shaley) (Fair Bleed)			
9.5	450	Shale			

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER
 ON ALL CORRESPONDENCE

Page: 1	Invoice: 10046133
Special : Instructions : Sale rep #: MAVERY MIKE	Time: 13:37:55 Ship Date: 12/17/12 Invoice Date: 12/17/12 Due Date: 01/05/13
Sold To: BOBCAT OILFIELD SRVC,INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053	Ship To: BOBCAT OILFIELD SRVC,INC (913) 837-2823 (913) 837-2823
Customer #: 3570021	Customer PO: Order By:

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

Burnis 8W-12

*Phone order by Bob
Direct Delivery*

INVOICE

913-837-4157

FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____ SHIP VIA MIAMI COUNTY RECEIVED COMPLETE AND IN GOOD CONDITION X	Freight	100.00	Sales total	\$4116.80
	Taxable	4216.80	Misc + Frgt	100.00
	Non-taxable	0.00	Sales tax	318.37
	Tax #		TOTAL	\$4535.17

2 - Customer Copy

