


Lease:	Burris	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4'
Longstring:	Cemented:	Hole Size:
487'Ft. Of 2 7/8 8rd	60 Sacks	5 5/8'



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: 9W-12
Location: NW NE SW SW S12 T17R24E
County: Miami
FSL: 1310
FEL: 4525
API#: 15-121-29376-00-00
Started: 12-13-12
Completed: 12-17-12

SN: NONE	Packer: NONE	TD: 490'FT
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	TD	490	Lime (Odor)
6	7	Clay			
24	31	Lime			
49	80	Shale			
11	91	Lime			
5	96	Shale			
11	107	Sand (Dry)			
13	120	Shale			
5	125	Lime			
21	146	Shale			
10	156	Shale (Oil Sand Streaks)			
3	159	Shale			
1	160	Oil Sand (Shaley) (Fair Bleed)			
10	170	Shale			
9	179	Lime			Surface 12-13-12
14	193	Shale			Set Time 5:00 PM
29	222	Lime			Called In 3:00 PM – Talked To Brooke
6	228	Black Shale			
21	249	Lime			Well TD – 490' Ft.
4	253	Black Shale			Long string 487'Ft. Of 2 7/8" 8rd Pipe
1	254	Lime			Set Time 3:00 PM – On 12-17-12
6	260	Shale			Called In 1:45 PM – Talked To Brooke
6	266	Lime			
4	270	Shale			
2	272	Shale (Limey)			
4	276	Sandy Shale (Odor)			
17	293	Shale			
19	312	Sand (Dry)			
62	374	Shale			
11	385	Sandy Shale (Odor)			
23	408	Shale			
1	409	Black Shale			
28	437	Shale			
11.5	448.5	Oil Sand (Some Shale) (Water) (Very Little Oil)			
2.5	451	Oil Sand (Some Shale) (Fair Bleed) (Slight Show Of Water)			
1.5	452.5	Oil Sand (Some Shale) (Fair Bleed) (Oil & Slight Show Of Water) (Fractured)			
3.5	456	Oil Sand (Oil & Water) (Some Shale) (Fair Bleed)			
1	457	Sandy Shale (Oil Sand Streaks) (Poor Bleed)			
8	465	Shale			
8	473	Lime			
12	485	Shale (Limey)			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 9W-12
Location: NW NE SW SW S12 T17 R24 E
County: Miami
FSL: 1310
FEL: 4525
API#: 15-121-29376-00-00
Started: 12-13-12
Completed: 12-17-12

Lease :	Burris
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	439	0:00	0	Oil Sand ("Water") (Very Little Oil)	448.5'
1	440	1:00	1		
2	441	2:00	1		
3	442	3:30	1.5		
4	443	5:00	1.5		
5	444	6:00	1		
6	445	7:30	1.5		
7	446	9:00	1.5		
8	447	10:30	1.5		
9	448	12:00	1.5		
10	449	13:30	1.5	Oil Sand (Some Shale) (Fair Bleed) (Slight Show Of Water)	451'
11	450	14:30	1		
12	451	16:30	2	Oil Sand ((Some Shale) (Oil & Slight Shaow Of Water) (Fractured)	452.5'
13	452	18:00	1.5		
14	453	19:30	1.5		
15	454	21:00	2		
16	455	22:30	1		
17	456	24:00	1.5	Oil Sand (Oil & Water) (Some Shale) (Fair Bleed)	456'
18	457	25:30	1.5		
18	457	25:30	1.5	Sandy Sahal (Oil Sand Streaks) (Poor Bleed)	457'
19	458	29:30	4	Shale	

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER ON ALL CORRESPONDENCE

Page: 1

Invoice: **10046133**

Special :		Time:	13:37:55
Instructions :		Ship Date:	12/17/12
		Invoice Date:	12/17/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	01/05/13

Sold To: BOBCAT OILFIELD SRVC, INC	Ship To: BOBCAT OILFIELD SRVC, INC
C/O BOB EBERHART	(913) 837-2823
30805 COLDWATER RD	
LOUISBURG, KS 66053	(913) 837-2823

Customer #: 3570021 Customer PO: Order By:

popimg01

6YH
T 26

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

*Burns
9W-12*

*Phone order by Bob
Direct Delivery*

INVOICE

913-837-4159

X	FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER		Sales total	\$4116.80	
	SHIP VIA MIAMI COUNTY				Freight	100.00	Misc + Frgt	100.00
	RECEIVED COMPLETE AND IN GOOD CONDITION				Taxable	4216.80	Sales tax	318.37
					Non-taxable	0.00		
					Tax #			

TOTAL \$4535.17

2 - Customer Copy

