

Lease:	Burris	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 503' Ft Of 2 7/8" 8rd	Cemented: 60	Hole Size: 5 5/8"


Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 10W-12
Location: NE NE SW SW S12 T17 R24E
County: Miami
FSL: 1310
FEL: 4192
API#: 15-121-29377-00-00
Started: 12-07-12
Completed: 12-11-12

SN: NONE	Packer: NONE	TD: 510' Ft.
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil			
4	5	Clay			
34	39	Lime			
49	88	Shale			
10	98	Lime			
4	102	Shale			
10	112	Gas Sand (Shaley)			
14	126	Shale			
5	131	Lime			
20	151	Shale			
9	160	Sandy Shale (Odor)			
17	177	Shale			
10	187	Lime			
15	202	Shale			
27	229	Lime			Surface 12-07-12
6	235	Black Shale			Set Time 11:30 AM
21	256	Lime			Called 9:25 AM – Talked To Brooke
4	260	Black Shale			
3	263	Lime			Well TD – 510' Ft.
5	268	Shale			Long string 503' 2 7/8" 8rd Pipe
5	273	Lime			Set Time 10:30 PM 12-11-12
3	276	Shale			Called 8:20 AM - Talked To Brooke
3	279	Shale (Limey)			
3	282	Oil Sand (Shaley) (Poor Bleed)			
20	302	Shale			
24	326	Sand (Dry)			
55	381	Shale			
12	393	Sandy Shale (Oil Sand Streak)			
25	418	Shale			
1	419	Black Shale			
29	448	Shale			
1	449	Shale (Limey)			
7.5	456.50	Oil Sand (Some Shale) (Water) (Very Little Oil)			
1.5	458	Oil Sand (Fractured) (Water) (Very Little Oil)			
4	462	Oil Sand (Water) (Very Little Oil) (Some Shale)			
3	465	Oil Sand (Oil & Some Water) (Fair Bleed) (Some Shale)			
.5	465.5	Oil Sand (Fractured) (Oil & Some Water) (Fair Bleed)			
.5	466	Lime			
2.5	468.5	Oil Sand (Soms Shale) (Fair Bleed)			
6.5	475	Shale			
4	479	Lime			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Lease :	Burris
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

Well #: 10W-12
Location: NE NE SW SW S12 T17 R24 E
County: Miami
FSL: 1310
FEL: 4192
API#: 15-121-29377-00-00
Started: 12-07-12
Completed: 12-11-12

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	451	0:00	0	Oil Sand (Water) (Very Little Oil)	456.5'
1	452				
2	453				
3	454				
4	455				
5	456				
6	457			Oil Sand (Fractured)(Water) (Very Little Oil)	458'
7	458				
8	459			Oil Sand (Water) (Very Little Oil) (Some Shale)	462'
9	460				
10	461				
11	462				
12	463			Oil Sand (Oil & Some Water) (Fair Bleed)	465'
13	464				
14	465				
15	466			Oil Sand (Fractured) (Some Oil & Water) (Fair Bleed)	465.5'
16				Lime (Core Locked Up Because Of Fracture) (Pulled Out And Begin To Core Again)	
17					
18					
19					
20					



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 10W-12
Location: NE NE SW SW S12 T17 R24 E
County: Miami
FSL: 1310
FEL: 4192
API#: 15-121-29377-00-00
Started: 12-07-12
Completed: 12-11-12

Core Run #2

Lease :	Burriss
Owner:	Bobcat oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	467	0:00	0	Oil Sand (Some Shale) (Fair Bleed)	468.5
1	468	1:00	1		
2	469	2:30	1.5	Shale	474.5'
3	470	4:30	2		
4	471	6:00	1.5		
5	472	9:00	3		
6	473	11:30	2.5		
7	474	14:00	3.5		
8	475	16:00	2	Lime	
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Avery Lumber

P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER ON ALL CORRESPONDENCE

Page: 1		Invoice: 10045770	
Special :		Time:	14:54:09
Instructions :		Ship Date:	11/28/12
		Invoice Date:	11/30/12
Sale rep #: MAVERY MIKE	Acct rep code:	Due Date:	01/05/13
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053		Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823	
Customer #: 3570021	Customer PO:	Order By: BOB	

STH
T 27

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	2489.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

OK RE

Burnis
10W-12
12-11-12

DIRECT DELIVERY
PHONE ORDER BY BOB

913-837-4159

	FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER		Sales total	\$4116.80
	SHIP VIA	MIAMI COUNTY			Freight	100.00	Misc + Frgt 100.00
	RECEIVED COMPLETE AND IN GOOD CONDITION				Taxable	4216.80	Sales tax 318.37
	X				Non-taxable	0.00	
					Tax #		

TOTAL \$4535.17

2 - Customer Copy

