

Lease:	BURRIS	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4"
Longstring:	Cemented:	Hole Size:
500'Ft. Of 27/8" 8rd.	62 Sacks	5 5/8"

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 23W-12
Location: NE,NW,SE,SW,S12,T17,R24
County: MIAMI
FSL:1009
FEL: 3544
API#: 15-121-29414-00-00
Started: 1/18/13
Completed: 1/21/13

SN: NONE	Packer: NONE
Plugged:	Bottom Plug:

TD: 505' Ft.

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	5	502	Lime
7	8	Clay	1	503	Black Shale
41	49	Lime	TD	505	Shale
49	98	Shale			
10	108	Lime			
7	115	Shale			
8	123	Sandy Shale (Good Oil Show)			
14	137	Shale			
5	143	Lime			
43	186	Shale			
7	193	Lime (Broken)			
15	208	Shale			
28	236	Lime			
5	241	Black Shale			
3	244	Shale (Limey)			
20	264	Lime			
3	267	Black Shale			
2	269	Lime			
6	275	shale			
4	279	Lime			SET SURFACE 1/18/2013
10	289	Shale (Limey)			SET TIME 4:00 PM
2	291	Sandy Shale (Oil Sand Streak)			CALLED IN 2:00 PM – TALKED TO BROOKE
4	295	Sandy Shale			WELL TD 505' FT.
6	301	Shale			LONG STRING 500' FT. OF 2 7/8" 8RD PIPE
15	316	Sand (Shaley) (Oil)			SET TIME 4:30 PM – 1/22/2013
5	321	Sandy Shale			CALLED IN 3:30 PM – TALKED TO BROOKE
104	425	Shale			
1	426	Black Shale			
29	455	Shale			
1	456	Sand (Shaley) (Water) (Lime Streak At Top)			
11	467	Oil Sand (Some Shale) (Water – Very Little Oil)			
.5	467.5	Limey			
2.5	470	Oil Sand (Water – Very Little Oil)			
2	472	Oil Sand (Oil & Water) (Fair Bleed)			
1	473	Oil Sand (Water) (Poor Bleed)			
1.5	474.5	Oil Sand (Water & Some Oil)			
1	475.5	Oil Sand (Water) (Very Little Oil)			
1	476.5	Oil Sand (Good Bleed) (Some Shale)			
9.5	486	Shale			
5	491	Lime			
6	497	Shale (Limey)			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 23W-12
Location: NE,NW,SE,SW,S12,T17,R24
County: MIAMI
FSL: 1009
FEL: 3544
API#: 15-121-29414-00-00
Started: 1/18/13
Completed: 1/22/13

Core Run #1

Lease :	BURRIS
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	458	0:00	-----		
1	459	1:00	1		
2	460	2:00	1		
3	461	3:00	1		
4	462	4:00	1		
5	463	5:00	1		
6	464	6:00	1		
7	465	7:00	1		
8	466	7:30	.5		
9	467	8:30	1		
				LIME	467.5'
10	468	10:00	1.5		
11	469	10:30	.5		
12	470	11:30	1		
13	471	12:00	.5		
14	472	12:30	.5		
15	473	13:30	1		
16	474	14:30	1		
17	475	15:00	.5		
18	476	16:00	1		
19	477	17:00	1		
20	478	18:30	1.5		
				SHALE	

Avery Lumber
 P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Customer Copy

INVOICE

PLEASE REFER TO INVOICE NUMBER ON ALL CORRESPONDENCE

Page: 1	Invoice: 10046461
Special :	Time: 11:16:09
Instructions :	Ship Date: 01/07/13
	Invoice Date: 01/11/13
Sale rep #: MAVERY MIKE	Acct rep code:
Due Date: 02/05/13	
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053	Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823
Customer #: 3570021	Customer PO:
	Order By: CLINT

5TH T 28 papimg01

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
380.00	380.00	L	BAG	CPPC	PORTLAND CEMENT	8.8900 BAG	8.8900	3378.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.7900 BAG	5.7900	1389.60
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

*Burnis
23W-12*

PHONE ORDER BY CLINT

DIRECT DELIVERY

INVOICE 913-837-4159

FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____ SHIP VIA MIAMI COUNTY RECEIVED COMPLETE AND IN GOOD CONDITION X	Freight	100.00	Sales total	\$5005.80
	Taxable	5105.80	Misc + Frgt	100.00
	Non-taxable	0.00	Sales tax	385.49
			TOTAL	\$5491.29

2 - Customer Copy

