



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 39031

LOCATION Ottawa

FOREMAN Alan Maden

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-20-12	4448	Guetterman #KRI-15 NW20	14	22	30	
CUSTOMER						
Kansas Resources E&D						
MAILING ADDRESS						
9393 W 110th						
CITY		STATE	ZIP CODE			
Overland Park		KS	66210			
TRUCK #	DRIVER	TRUCK #	DRIVER			
516	AlaMad	Safety	Meet			
368	Art Mad					
369	Der Mas	DM				
558	Bre Man	BM				

JOB TYPE long string HOLE SIZE 5 7/8 HOLE DEPTH 915 CASING SIZE & WEIGHT 2 7/8  
 CASING DEPTH 905 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING yes  
 DISPLACEMENT 5 1/4 DISPLACEMENT PSI 800 MIX PSI 200 RATE 4 bpm

REMARKS: Held meeting Established rate. Pipe jacked out of hole broke fitting on casing + casing fell into hole. Put rig back over well. Spearred casing + pulled back to surface. Rig blew through casing. Established rate again. Mixed + pumped 100# gel followed by 124 slk 50150 cement plus 2% gel + 1/2# phenoseal per sack. Circulated cement. Flushed pump. Pumped 2 plugs to casing TD well held 800 PST. Set float. Closed valve. Had gas or air bubbles coming to surface. Bubbles were slowly dying down as we left.

Evans, Mitchell

Alan Maden

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL	
5401	1	PUMP CHARGE	368	1030.00	
5406	30	MILEAGE	368	120.00	
5402	905	casing footage	368		
5407	min	ton miles	558	350.00	
5502C	3 1/2	80 vac	369	315.00	
1124	124	50150 cement		1357.80	
1118B	308 #	gel		64.68	
1107A	62 #	phenoseal		79.98	
4402	2	2 1/2 plug		56.00	
				SALES TAX	117.27
				ESTIMATED TOTAL	3490.73

SCANNED

completed

Form 3737

AUTHORIZATION \_\_\_\_\_

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

155555