



**CONSOLIDATED**  
Oil Well Services, LLC

TICKET NUMBER 38991

LOCATION Ottawa KS.

FOREMAN Fred Mader

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT  
CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12/7/12	<del>25519</del>	Guetterman # KRJ23	NE 30	14	22	JO
CUSTOMER Kausas Resources Expl & Dev 4448			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 9393 W 110th St.			506	Fred Mad	Safety	MK
CITY Overland Park			495	Nay Bec	HB	2
STATE KS			370	Ki Cav	KC	
ZIP CODE 66240			503	Dan Det	DD	

JOB TYPE Long string HOLE SIZE 5 7/8 HOLE DEPTH 883 CASING SIZE & WEIGHT 2 3/8 EUE  
 CASING DEPTH 873 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 5.07 BBL DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5 BPM

REMARKS: Establish pump rate. Mix + Pump 100# Gel Flush. Mix + Pump  
 120 sks 50/50 Por Mix Cement 2% Gel 1/2" Pheno Seal/sk.  
 Cement to surface. Flush pump + lines clean. Displace 20' 2 1/2"  
 rubber plug to casing TD. Pressure to 800+ PSI. Release  
 pressure to set float valve. Shut in casing.

Evans Energy Dev. Inc. - Mitchell

*Fred Mader*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	1030 <sup>00</sup>
5406	30mi	MILEAGE	495	120 <sup>00</sup>
5402	873'	Casing Footage		N/C
5407	Minimum	Ton Miles	503	350 <sup>00</sup>
5502C	2 hrs	80 BBL Vac Truck	370	180 <sup>00</sup>
1124	120 sks	50/50 Por Mix Cement		1314 <sup>00</sup>
1118B	302#	Premium Gel		63 <sup>42</sup>
1107A	60#	Pheno Seal		77 <sup>40</sup>
4402	2	2 1/2" Rubber Plugs		56 <sup>00</sup>
			7.525767220	SALES TAX
				ESTIMATED TOTAL
				113 <sup>68</sup>
				3304 <sup>50</sup>

completed

*[Signature]*

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this fo

255185