


Lease:	Light	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4
Longstring:	Cemented:	Hole Size:
317'	50 sacks	5 5/8
2 7/8 8rd		



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: B-5
Location: SW NW NE NW Sec8 Twp20S R23E
County: Linn
FSL:4950
FEL: 3960
API#: 15-107-24706
Started: 4-08-2013
Completed: 4-09-2013

SN: None	Packer: None	TD: 320'
Plugged: None	Bottom Plug: None	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil and Loose Rock			
12	13	Lime			
3	16	Shale			
3	19	Black Shale			
4	23	Shale			
16	39	Lime			
3	42	Shale			
2	44	Black Shale			
3	47	Lime			
3	50	Shale			
6	56	Lime			
1	57	Black Shale			
2	59	Shale			
4	63	Lime			
116	179	Shale			
1	180	Black Shale			
26	206	Shale			
1	207	Black Shale			
9	216	Shale			
7	223	Lime			
19	242	Shale(Flow)			
11	253	Lime(Good Oil Show)			SET SURFACE 4-08-2013
2	255	Shale(Limey)			SET TIME 1:30 P.M.
11	266	Sand(Gas w/Slight Oil Show)(Some Shale)			CALLED IN 11:30 A.M. TALKED TO Brook
3	269	Oil Sand(Fair Bleed)			WELL TD 320' FT.
3	272	Oil Sand(Good Bleed)			LONG STRING 317'FT OF 2 7/8" 8RD PIPE
1	273	Lime			SEAT NIPPLE - NONE
1	274	Sandy Shale			SET TIME 1:00 P.M. 4-09-2013
1.5	275.5	Oil Sand(Good Bleed)(some Shale)			CALLED IN 11:45 A.M. TALKED TO Ryan
2	277.5	Oil Sand(Shaley)(Good Bleed)			
1.5	279	Oil Sand(Good Bleed)			
6	285	Oil Sand(Very Shaley)(Fair Bleed)			
2	287	Oil Sand(Some Shale)(Good Bleed)			
3	290	Oil Sand(Very Shaley)(Fair Bleed)			
15	305	Shale			
3	308	Coal			
3	311	Shale			
TD	320	Lime			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: B-5
Location: SW NW NE NW Sec8 Twp20S R23E
County: Linn
FSL: 4950
FEL: 3960
API#: 15-107-24706
Started: 4-08-2013
Completed: 4-09-2013

Core Run #1

Lease :	Light
Owner:	Bobcat Oilfield Services, Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	261		-----	Sand(Gas w/Slight Oil Show)(Some Shale)	266'
1	262		1/4		
2	263		1/4		
3	264		1/2		
4	265		1/4		
5	266		3/4	Oil Sand(Fair Bleed)	269'
6	267		3/4		
7	268		3/4		
8	269		3/4	Oil Sand(Good Bleed)(Bottom 6" Slightly Limey)	272'
9	270		1		
10	271		1 1/4		
11	272		2	Lime	273'
12	273		1 1/2		
13	274		1/2	Sandy Shale	274'
14	275		1/2	Oil Sand(Good Bleed)	275.5'
15	276		1	Oil Sand(Shaley)(Good Bleed)	277.5'
16	277		1		
17	278		1	Oil Sand(Good Bleed)	279'
18	279		1/2	Oil Sand(Very Shaley)(Fair Bleed)	
19	280		1/2		
20	281		1		



1/2 Mile North of Louisburg
27295 Matcalf Rd.
P.O. Box 729
Louisburg, Kansas 66053
913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CERK	DATE	TIME
251		22015	PO # 22015 ORDR # 7221	NET 10TH	NR	4/12/13	7:55

ROBERT OHL
3000 COLONNATE ROAD
LOUISBURG, KS 66053

303 S. SPRING VALLEY ROAD
EAST 17th NORTH SIDE
913-265-0873

DEL. DATE: 4/ 3/13 TERM#551
SLSPR: RR ROBERT RAND
TAX : 001 LOUISBURG, KS
DOC# 177937

* INVOICE *

ORDR 72221

LUMBER COMPANY LUMBER 913-837-2955 / 1

QUANTITY SHIPPED	QUANTITY ORDERED	DM	SKU	DESCRIPTION	UNITS	PRICE PER	EXTENSION
245	1	EA	PORTLAND	94# PORTLAND CEMENT 1/11	245	9.00 /EA	2,205.00
280	1	EA	FLYASH	80# SX FLY ASH	280	5.20 /EA	1,456.00
14	1	EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14	1	EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL	FUEL SURCHARGE	1	48.55 /EA	48.55

*Light
BEST*

** AMOUNT CHARGED TO STORE ACCOUNT **	4,340.63	TAXABLE	3989.55
		NON-TAXABLE	0.00
		SUBTOTAL	3989.55
		TAX AMOUNT	351.08
		TOTAL CHARGE	4340.63

X

RECEIVED BY: