


Lease:	LIGHT	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4"
Longstring:	Cemented:	Hole Size:
326'FT. OF 2 7/8 8rd	50 SACKS	5 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991




Well #: A-5
Location: NE,NE,NW,NW,S8,T20,R23E
County: LINN
FSL: 5115' FT
FEL: 4125' FT
API#: 15-107-24701-00-00
Started: 4/09/13
Completed: 4/16/13

SN: 264' FT.	Packer: NONE
Plugged:	Bottom Plug:

TD: 330' FT.

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOP SOIL			
14	15	LIME			
3	18	SHALE			
3	21	BLACK SHALE			
5	26	SHALE			
19	45	LIME			
3	48	SHALE			
2	50	BLACK SHALE			
2	52	LIME			
5	57	SHALE			
5	62	LIME			
1	63	BLACK SHALE			
3	66	SHALE			
1	67	LIME			
147	214	SHALE			
1	215	BLACK SHALE			
8	223	SHALE			
7	230	LIME			
17	247	SHALE			SET SURFACE 4/09/13
7	254	SHALE (LIME STREAK)			SET TIME 2:00 P.M.
6	260	LIME			CALLED IN 11:45 A.M. TALKED TO RYAN
4	264	SHALE (LIMEY)			WELL TD 330' FT.
2	266	SANDY SHALE (OIL SAND STREAK)			LONG STRING 326'FT. OF 2 7/8" 8RD PIPE
2	268	OIL SAND (VERY SHALEY) (POOR BLEED)			SET TIME 1:00P.M. 4/16/13
1	269	LIME			CALLED IN 12:00 P.M. TALKED TO DIANN
5	274	OIL SAND (FAIR BLEED)			
4	278	OIL SAND (GOOD BLEED)			
2	280	SANDY SHALE			
1	281	OIL SAND (GOOD BLEED)			
.5	281.5	SHALE			
1.5	283	OIL SAND (GOOD BLEED)			
.5	283.5	SHALE			
3.5	287	OIL SAND (HEAVY BLEED) (SOME SHALE)			
4	291	SANDY SHALE (SOME OIL SAND STREAKS) (SOME LENSES SHOW A FAIR BLEED)			
2	293	OIL SAND (SHALEY) (GOOD BLEED)			
2	295	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)			
14	309	SHALE			
3	312	COAL			
5	317	SHALE			
11	328	LIME			
TD	330	SHALE			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: A-5
Location: NE,NW,NE,NW,S8,T20,R23E
County: LINN
FSL: 5115'
FEL: 3508'
API#: 15-107-24699-00-00
Started:3/19/13
Completed: 3/20/13

Core Run #1

Lease :	LIGHT
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	276	0:00	-----		
1	277	0:30	.5	OIL SAND (GOOD BLEED) (SLIGHT SHOW OF WATER)	278' FT
2	278	1:00	.5		
3	279	1:30	.5	SANDY SHALE	280' FT
4	280	2:30	1		
5	281	3:00	.5	OIL SAND (GOOD BLEED)	281' FT
				SHALE	281.5' FT
6	282	4:00	1	OIL SAND (GOOD BLEED)	283' FT
7	283	5:00	1	SHALE	283.5' FT
8	284	6:00	1		
9	285	7:00	1		
10	286	9:00	2	OIL SAND (HEAVY BLEED) (SOME SHALE)	287' FT
11	287	10:30	1.5		
12	288	12:00	1.5		
13	289	13:30	1.5	SANDY SHALE (SOME OIL SAND STREAKS) (SOME LENSES SHOW A FAIR BLEED)	291' FT
14	290	16:00	2.5		
15	291	18:00	2		
16	292	19:30	1.5	OIL SAND (SHALEY) (GOOD BLEED)	293' FT
17	293	20:30	1		
18	294	22:00	1.5	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	295' FT
19	295	23:00	1		
20	296	24:30	1.5	SHALE	



1/2 Mile North of Louisburg
27295 Malcott Rd.
P.O. Box 729
Louisburg, Kansas 68053
913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

PAGE NO 1

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLEAR	DATE	TIME
251		22015	PO # 22015 GRN # 7221	NET 10TH	RR	4/12/13	7:55

ROBERT OTI
3005 CALDWELL ROAD
LOUISBURG, KS 68053

303 S. SPRING VALLEY ROAD
EAST 174N NORTH SIDE
913-265-0873

DEL. DATE: 4/ 3/13 TERM#551

INVOICE #

BLSPR: RR ROBERT RAND
TAX : 001 LOUISBURG, KS
ORDER 72221

QUANTITY	ORDERED	DM	SKU	DESCRIPTION	UNITS	PRICE PER	EXTENSION
245	1	EA	PORTLAND	94# PORTLAND CEMENT 1/11	245	9.00 /EA	2,205.00
280	1	EA	FLYASH	80# SX FLY ASH	280	5.20 /EA	1,456.00
14	1	EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14	1	EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL	FUEL SURCHARGE	1	48.55 /EA	48.55

*Light
Ash*

** AMOUNT CHARGED TO STORE ACCOUNT **	4,340.63	TAXABLE	3989.55
		NON-TAXABLE	0.00
		SUBTOTAL	3989.55
		TAX AMOUNT	351.08
		TOTAL AMOUNT	4340.63

RECEIVED BY:

FROM MOSSMAN LUMBER 9138375871

D-50-1999 8:59PM

X