



**CONSOLIDATED**  
Oil Well Services, LLC

258043

TICKET NUMBER 41799  
LOCATION Ottawa KS  
FOREMAN Fred Mader

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4/12/13	4448	Guetherman # KRI-20	NW 20	14	22	JO

  

CUSTOMER	TRUCK #	DRIVER	TRUCK #	DRIVER
Kansas Resources Expl & Dev. MAILING ADDRESS 9393 W 110th St Overland Park KS 66210	712	Fred Mader	Safety	Mader
	495	Harbec	HB	
	370	Kei Car	KC	
	548	Mikhaa	MH	

JOB TYPE Longstring HOLE SIZE 5 7/8 HOLE DEPTH 879 CASING SIZE & WEIGHT 2 7/8 EUE  
 CASING DEPTH 883' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 2 1/2" Plug  
 DISPLACEMENT 5.13 BBL DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5BPM

REMARKS: Hold crew meeting. Establish pump rate. Mix + Pump 200# Gel  
Flush. Mix + Pump 107 sks 50/50 Por Mix Cement 2% Gel 1/2" Phenol  
Seal. Cement to surface. Flush pump + lines clean. Displace  
2. 2 1/2" Rubber plugs to casing TD. Pressure to 800# PSI. Release  
pressure to set float valve. Shut in casing.

*Fred Mader*

Evans Energy Dev. Inc - Mitchell.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	1030 <sup>00</sup>
5406	.30 mi	MILEAGE	495	120 <sup>00</sup>
5402	883	Casing Footage		N/C
5407	Minimum	Ten Miles	548	350 <sup>00</sup>
5502C	3 hrs	50 BBL 50 Vac.	370	270 <sup>00</sup>
1124	117 SKS	50/50 Por Mix Cement		1281 <sup>15</sup>
1118B	397 #	Premium Gel		833 <sup>2</sup>
1107A	59 #	Pheno Seal		76 <sup>11</sup>
4402	2	2 1/2" Rubber Plug		56 <sup>00</sup>
			7.525%	SALES TAX
				ESTIMATED TOTAL
				112 <sup>62</sup>
				3379 <sup>25</sup>

**completed**

*[Signature]*

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.