



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 43230

LOCATION Eureka

FOREMAN Rick Ladford

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-25-13	4768	Troy Burke 1-12E				Woodson
CUSTOMER <u>Leis Oil Services</u>			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS <u>1410 150th Rd</u>			445	Dave		
CITY <u>Yates Center</u>			515	Merle		
STATE <u>KS</u>			88	Rudy M. (M) (Co. TRK)		
ZIP CODE <u>66783</u>						

JOB TYPE LIS 0 HOLE SIZE 6 7/8" HOLE DEPTH _____ CASING SIZE & WEIGHT _____
 CASING DEPTH 1240 DRILL PIPE _____ TUBING 2 7/8" OTHER _____
 SLURRY WEIGHT 13.8" SLURRY VOL 55 Bbl WATER gal/sk 7.0 CEMENT LEFT in CASING _____
 DISPLACEMENT 7.2 DISPLACEMENT PSI 300 MIX PSI 700 Bump plugs RATE _____

REMARKS: Safety meeting. Rig up to 2 7/8 tubing. Pump 500# gel-flush, hook up to rigs mud pump, brought gel to surface. Rig up to cement. Mixed 205 sks 60/46 Perm mix cement w/ 4% 170 cacce + 1# phenseal/sk @ 13.8"/gal. Shut down, washout pump & lines, stuff 2 plugs. Displace w/ 7.2 Bbl fresh water. Final pump pressure 300 PSI. Bump plug to 700 PSI. Close well in @ 300 PSI. Good cement returns to surface - 6 Bbl slurry to pit. Job complete Rig down.

Thank You

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	1085.00	1085.00
5406	40	MILEAGE	4.20	168.00
5502C	3 1/2 hrs	80 Bbl VAC TRK	90.00	315.00
1131	205 sks	60/46 Perm mix cement	13.18	2701.90
1118B	705#	4% gel	.22	155.10
1102	175#	170 cacce	.78	136.50
1107A	205#	1# phenseal/sk	1.35	276.75
1118B	500#	gel-flush	.22	110.00
5407	8.8	ton mileage bulk tax	1.41	496.32
1123	3000 gals	city water	17.30/1000	51.90
4402	2	2 7/8" top rubber plug	29.50	59.00
		<u>\$ 5810.32</u>		
		<u>-5% 290.52</u>		
		<u>\$ 5519.80</u>		
			Subtotal	5555.47
			SALES TAX <u>7.3%</u>	254.85
			ESTIMATED TOTAL	5810.32

Ravin 3737

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.