


Lease:	BURRIS	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 511' FT. OF 2 7/8 8rd	Cemented: 60 SACKS	Hole Size: 5 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: 19W-12
Location: SW,NW,SE,SW,S12,T17,R24
County: MIAMI
FSL:678'FT
FEL: 3830'FT
API#: 15-121-29502-00-00
Started: 7/12/13
Completed: 7/15/13
TD: 515' FT.

SN: NONE	Packer: NONE
Plugged:	Bottom Plug:

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOP SOIL	3	510	SHALE
7	8	CLAY	1	511	LIME
17	25	LIME	TD	515	SHALE
1	76	CLAY			
37	63	LIME			
58	111	SHALE			
9	120	LIME			
11	131	SHALE			
4	135	SAND (SHALEY) (OIL SHOW AT TOP)			
14	149	SHALE			
6	155	LIME			
41	196	SHALE			
1	197	LIME			
6	203	SHALE			
8	211	LIME			
16	227	SHALE			
26	253	LIME			
2	255	SHALE			
4	259	BLACK SHALE			SET SURFACE 7/12/13
22	281	LIME			SET TIME 1:30 P.M.
5	286	BLACK SHALE			CALLED IN 12:30 P.M. TALKED TO BROOKE
1	287	LIME			WELL TD 515' FT.
4	291	SHALE			LONG STRING 511' FT. OF 2 7/8" 8RD PIPE
6	297	LIME			SET TIME 3:00 P.M. 7/15/13
9	306	SHALE (LIMEY)			CALLED IN 2:00 P.M. TALKED TO BROOKE
8	314	SANDY SHALE (OIL SHOW)			
38	352	SHALE			
6	358	SAND (WATER)			
148	406	SHALE			
10	416	SANDY SHALE (VERY SLIGHT OIL SHOW)			
23	439	SHALE			
2	441	BLACK SHALE			
28	469	SHALE			
2	471	OIL SAND (SHALEY) (FAIR BLEED)			
5	476	OIL SAND (SOME SHALE) (FAIR BLEED)			
4	480	OIL SAND (WATER) (VERY LITTLE OIL)			
7	487	OIL SAND (OIL & WATER) (15% OIL & 85% WATER)			
3	490	OIL SAND (WATER) (VERY LITTLE OIL)			
1	491	BLACK SAND (SOME OIL & WATER) (FAIR BLEED)			
11	503	SHALE			
4	507	LIME			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 19w-12
Location: SW, NW, SE, SW
County: MIAMI
FSL: 678
FEL: 3830
API#: 15-121-29502-00-00
Started: 7/12/13
Completed: 7/15/13

Core Run #1

Lease :	BURRIS
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	471	0:00	-----		
1	472	1:00	1		
2	473	2:00	1		
3	474	3:00	1	OIL SAND (SOME SHALE) (FAIR BLEED)	476' FT
4	475	4:00	1		
5	476	5:00	1		
6	477	5:30	.5		
7	478	6:00	.5	OIL SAND (WATER) (VERY LITTLE OIL)	480' FT
8	479	6:30	.5		
9	480	7:30	1		
10	481	8:00	.5		
11	482	9:00	1		
12	483	9:30	.5		
13	484	10:30	1	OIL SAND (OIL & WATER) (FAIR BLEED) (15% OIL & 85% WATER)	487' FT
14	485	11:30	1		
15	486	12:00	.5		
16	487	12:30	.5		
17	488	13:30	1	OIL SAND (WATER) (VERY LITTLE OIL)	490' FT
18	489	14:00	.5		
19	490	15:00	1		
20	491	16:00	1	BLACK SAND (OIL & SOME WATER) (FAIR BLEED)	



1/2 Mile North of Louisburg
27295 Metcalf Rd.
P.O. Box 729
Louisburg, Kansas 66053
913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

PRSE NO: 1

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
81				NET 10TH	RR	6/28/13	12:38

ROBERT OR
2425 WILMINGTON ROAD
LOUISBURG, KS 66053

11498 WEST 152 HIGHWAY

DEL. DATE: 6/ 6/13 TERMS: S1

DOC# 73582

* ORDER *

SLSPR: RR ROBERT ROND

TAX : 001 LOUISBURG, KS

ORDER 73582

QUANTITY	UNIT	DESCRIPTION	LOCATION	PRICE	EXTENSION
280	EA	PORTLAND CEMENT 1711	BARN1	9.00 /EA	2,520.00
245	EA	800 5X FLY ASH	BARN1	5.20 /EA	1,274.00
14	EA	RETURNABLE PALLET	ROAD	15.00 /EA	210.00 *
14	EA	SHRINK WRAPPED PALLET		5.00 /EA	70.00
1	EA	FUEL SURCHARGE	ROAD	48.55 /EA	48.55
				TAXES	4122.55
				** DEPOSIT AMOUNT **	0.00
				** BALANCE DUE **	4,485.33
RECEIVED BY				** PAYMENT RECEIVED **	0.00
				TAX AMOUNT	362.78
				TOTAL AMOUNT	4485.33

*Barris
19W-12*