


| | | |
|--|-------------------------------|----------------------|
| Lease: | LIGHT | |
| Owner: | Bobcat Oilfield Services Inc. | |
| OPR #: | 3895 | |
| Contractor: | DALE JACKSON PRODUCTION CO. | |
| OPR #: | 4339 | |
| Surface: 20' of 6" | Cemented: 5 Sacks | Hole Size: 8 3/4" |
| Longstring: 348'FT. OF 2 7/8 8rd | Cemented: 50 SACKS | Hole Size: 5 5/8" |



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

| |
|--|
| Well #: F-6 |
| Location: NE,NW,NW,NW, Sec.8, Twp.20S, Rg.23E |
| County: LINN |
| FSL: 4308' FT |
| FEL: 4006' FT |
| API#: 15-107-24863-00-00 |
| Started: 9/04/13 |
| Completed: 9/06/13 |

| | |
|---------------------------------|---|
| SN: NONE | Packer: NONE |
| Plugged: Lower With 70 Sacks | Bottom Plug: From 350' Ft. To 859' Ft. |

| |
|--------------|
| TD: 859' FT. |
|--------------|

Well Log

| TKN | BTM Depth | Formation | TKN | BTM Depth | Formation |
|-----|-----------|--|-----|-----------|--|
| 1 | 1 | TOP SOIL | 3 | 429 | LIGHT SHALE |
| 25 | 26 | LIME | 12 | 441 | LIGHT SANDY SHALE |
| 4 | 29 | SHALE | 11 | 452 | SANDY SHALE |
| 2 | 31 | BLACK SHALE | 9 | 463 | SHALE |
| 5 | 36 | SHALE (LIMEY) | 2 | 465 | LIME |
| 15 | 51 | LIME | 11 | 476 | DARK SHALE |
| 4 | 55 | SHALE | 2 | 478 | LIME |
| 3 | 58 | BLACK SHALE | 11 | 489 | DARK SHALE |
| 2 | 60 | LIME | 1 | 490 | LIME (ODOR) |
| 5 | 65 | SHALE | 2 | 492 | DARK SANDY SHALE (GAS SAND STREAK) (SLIGHT OIL SHOW) |
| 6 | 71 | LIME | 3 | 495 | DARK SANDY SHALE |
| 1 | 72 | BLACK SHALE | 9 | 504 | DARK SHALE |
| 4 | 76 | SHALE | 1 | 505 | COAL |
| 5 | 81 | LIME | 6 | 511 | LIGHT SHALE |
| 110 | 191 | SHALE | 11 | 522 | DARK SHALE |
| 10 | 201 | LIGHT SHALE (LIMEY) | 5 | 527 | LIME |
| 18 | 219 | SHALE | 3 | 530 | BLACK SHALE |
| 1 | 220 | COAL | 8 | 538 | LIGHT SHALE |
| 10 | 230 | LIGHT SHALE | 12 | 550 | LIGHT SANDY SHALE |
| 6 | 236 | LIME (SHALEY) | 10 | 560 | DARK SHALE |
| 20 | 256 | SHALE | 3 | 563 | COAL |
| 12 | 268 | LIME | 10 | 573 | LIGHT SHALE |
| 18 | 286 | SHALE | 19 | 592 | DARK SHALE |
| 3 | 289 | GAS SAND (WATER) (FAIR OIL SHOW) | 2 | 594 | COAL |
| 4 | 293 | OIL SAND (SHALEY) (FAIR BLEED) (WATER) | 7 | 611 | SHALE |
| 2 | 295 | OIL SAND (VERY SHALEY) (GOOD BLEED) | 5 | 616 | LIGHT SANDY SHALE |
| 2 | 297 | OIL SAND (SHALEY) (GOOD BLEED) | 12 | 628 | DARK SHALE |
| 2 | 299 | OIL SAND (VERY SHALEY) (FAIR BLEED) | 3 | 631 | LIGHT SHALE |
| 16 | 315 | SHALE | 1 | 632 | COAL |
| 2 | 317 | COAL | 12 | 644 | SHALE |
| 6 | 323 | SHALE | 5 | 649 | LIGHT SANDY SHALE |
| 9 | 332 | LIME | 1 | 650 | COAL |
| 9 | 34. | SHALE | 9 | 659 | LIGHT SHALE |
| 4 | 347 | LIME | 12 | 671 | SANDY SHALE (DRY SAND STRIPS) |
| 4 | 351 | BLACK SHALE | 4 | 675 | LIGHT SHALE |
| 8 | 359 | DARK SHALE | 10 | 685 | SHALE |
| 8 | 367 | SAND (DRY) (LIMEY) | 3 | 688 | SAND (SHALEY) (DRY) |
| 9 | 376 | LIGHT SHALE | 4 | 692 | SAND (DRY) |
| 10 | 386 | LIME | 4 | 696 | SAND (SHALEY) (DRY) |
| 7 | 393 | SHALE (LIMEY) | 11 | 707 | SHALE |
| 7 | 400 | SHALE | 1 | 708 | COAL |
| 8 | 408 | LIME | 32 | 740 | SHALE |
| 5 | 413 | BLACK SHALE | 6 | 746 | SANDY SHALE |
| 6 | 419 | SHALE | 47 | 793 | SAND (SOME SHALE) (DRY) |
| 6 | 425 | SHALE (LIMEY) | 1 | 794 | COAL |
| 1 | 426 | BLACK SHALE | 5 | 799 | SHALE |



MOSSMAN LUMBER COMPANY

1/2 Mile North of Louisburg
27295 Meical Rd.
P.O. Box 720
Louisburg, Kansas 66053
913-837-2955 • 1-800-521-1764

PAGE NO 1

True Value.

| CUSTOMER NO. | JOB NO. | PURCHASE ORDER NO. | REFERENCE | TERMS | CLERK | DATE | TIME |
|--------------|---------|--------------------|-------------|----------|-------|---------|------|
| 253 | | | ORDER 75328 | NET 10TH | RR | 8/31/13 | 2:37 |

NEED OIL
3000S CULTIVATOR HOPE
LOUISBURG, KS 66053

W 114th WEST 152 HENRY
P 7th E 152 EAST

DEL. DATE: 8/31/13 TERMS: S1
SLSPR: RR ROBERT ROND
TAX : 001 LOUISBURG, KS

DOC# 178508

INVOICE #

ORDR 75328

| QUANTITY | ORDERED | DEL | SKU | DESCRIPTION | UNITS | PRICE/PER | EXTENSION |
|----------|---------|-----|----------|---|-------|-----------|-----------|
| 320 | | EA | FLYASH | 80# SX FLY ASH | 320 | 5.20 /EA | 1,664.00 |
| 210 | | EA | PORTLAND | 94# PORTLAND CEMENT 1/11 70.00 Cancelled | 210 | 9.00 /EA | 1,890.00 |
| 14 | | EA | PALLET | RETURNABLE PALLET | 14 | 17.00 /EA | 238.00 * |
| 14 | | EA | WRAP | SHRINK WRAPPED PALLET | 14 | 5.00 /EA | 70.00 |
| 14 | | EA | FUEL | FUEL SURCHARGE | 14 | 48.55 /EA | 679.70 |

O/R E

** AMOUNT CHARGED TO STORE ACCOUNT ** 4,934.56
TAXABLE 4541.70 *
NON-TAXABLE 0.00
SUBTOTAL 4541.70

RECEIVED BY

TAX AMOUNT 392.86
TOTAL 4934.56

P. 1
187-25-1333 3:45AM
FROM MOSSMAN LUMBER 9138375871