



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61  
P.O. Box 8613  
Pratt, Kansas 67124  
Phone 620-672-1201

FIELD SERVICE TICKET  
1718 04493 A

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

|                    |       |                                       |     |  |     |                            |          |      |
|--------------------|-------|---------------------------------------|-----|--|-----|----------------------------|----------|------|
| DATE OF JOB 9-1-11 |       | DISTRICT KANSAS                       |     | NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.: |     |                            |          |      |
| CUSTOMER FG Holl   |       | LEASE LeRoy Farm Trust #1-30 WELL NO. |     |  |     |                            |          |      |
| ADDRESS            |       | COUNTY Barton 30-19-14 STATE KANSAS   |     |  |     |                            |          |      |
| CITY               |       | STATE                                 |     | SERVICE CREW Allen, Joe, T.J., Jr.   |     |                            |          |      |
| AUTHORIZED BY      |       | JOB TYPE: 5 1/2" L.S.                 |     |  |     |                            |          |      |
| EQUIPMENT#         | HRS   | EQUIPMENT#                            | HRS | EQUIPMENT#   | HRS | TRUCK CALLED 9-1-11        | DATE     | TIME |
| 28443              | 1 1/2 |                                       |     |  |     | ARRIVED AT JOB             | 9-1-11   | 1830 |
| 33708-20920        | 1 1/2 |                                       |     |  |     | START OPERATION            |          | 200  |
| 19831-19862        | 1 1/2 |                                       |     |  |     | FINISH OPERATION           |          | 330  |
|                    |       |                                       |     |  |     | RELEASED                   |          | 430  |
|                    |       |                                       |     |  |     | MILES FROM STATION TO WELL | 65 miles |      |

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: Rob Sorensen  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

| ITEM/PRICE REF. NO. | MATERIAL, EQUIPMENT AND SERVICES USED | UNIT | QUANTITY | UNIT PRICE | \$ AMOUNT |
|---------------------|---------------------------------------|------|----------|------------|-----------|
| CP105               | AA2 cement                            | SK   | 130      |            |           |
| CP103               | 60/40 Poz                             | SK   | 50       |            |           |
| CC102               | cell FLAKE                            | lb   | 33       |            |           |
| CC105               | Defoamer Powder                       | lb   | 31       |            |           |
| CC111               | SALT Fine                             | lb   | 586      |            |           |
| CC115               | Gas Blok                              | lb   | 123      |            |           |
| CC129               | F/A-322                               | lb   | 123      |            |           |
| CC201               | Gilsonite                             | lb   | 1675     |            |           |
| CF907               | Latch dump Plug + Baffle 5/2 Blue     | EA   | 1        |            |           |
| CF1251              | Auto Fill Float Shoe 5/2 Blue         | EA   | 1        |            |           |
| CF1651              | Turbolizer 5/2 Blue                   | EA   | 10       |            |           |
| CF1901              | 5/2 Basket Blue                       | EA   | 2        |            |           |
| CF2002              | Cement Scratchers                     | EA   | 50       |            |           |
| CC154               | Super flush                           | gal  | 500      |            |           |

| CHEMICAL / ACID DATA: |  |  |  |
|-----------------------|--|--|--|
|                       |  |  |  |
|                       |  |  |  |
|                       |  |  |  |

|                     |            |
|---------------------|------------|
| SERVICE & EQUIPMENT | %TAX ON \$ |
| MATERIALS           | %TAX ON \$ |

SUB TO: ALS

SERVICE REPRESENTATIVE Allen Wood

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: Rob Sorensen  
(WELL OWNER OPERATOR CONTRACTOR)

FIELD SERVICE ORDER NO.



|                              |                  |                               |                |
|------------------------------|------------------|-------------------------------|----------------|
| Customer<br>EGHoll           | Lease No.        | Date<br>9-1-11                |                |
| Lease<br>LeRoy Farming Trust | Well #<br>1-30   |                               |                |
| Field Order #<br>04493A      | Station<br>Pratt | Casing<br>5/2"                | Depth<br>3534' |
| Type Job<br>5/2" L.S.        | Formation<br>CNU | County<br>Barton              | State<br>KS    |
|                              | TD<br>3541       | Legal Description<br>30-19-14 |                |

| PIPE DATA             |              | PERFORATING DATA |           | FLUID USED |             | TREATMENT RESUME |              |                          |
|-----------------------|--------------|------------------|-----------|------------|-------------|------------------|--------------|--------------------------|
| Casing Size<br>5/2"   | Tubing Size  | Shots/Ft         | 25 SKS    | Acid       | 60/40 P02   | RATE             | PRESS        | ISIP                     |
| Depth<br>3534'        | Depth        | From             | To 30 SKS | Pre Pad    | AA2 @ 15"   | Max              |              | 5 Min.                   |
| Volume<br>34 BBL      | Volume       | From             | To 12 BBL | Pad        | super-flush | Min              |              | 10 Min.                  |
| Max Press<br>1200     | Max Press    | From             | To        | Frac       |             | Avg              |              | 15 Min.                  |
| Well Connection<br>PC | Annulus Vol. | From             | To 30 SK  |            | 60/40 RH    | HHP Used         | 20 SKS 60/40 | Annulus Pressure<br>M.H. |
| Plug Depth<br>3534'   | Packer Depth | From             | To        | Flush      | Disp. H2O   | Gas Volume       |              | Total Load               |

|                                     |                           |                  |
|-------------------------------------|---------------------------|------------------|
| Customer Representative<br>Rob Long | Station Manager<br>Scotty | Treater<br>Allen |
|-------------------------------------|---------------------------|------------------|

|               |       |       |        |       |        |    |  |  |  |
|---------------|-------|-------|--------|-------|--------|----|--|--|--|
| Service Units | 28443 | 33708 | 20920  | 19831 | 19862  |    |  |  |  |
| Driver Names  | Allen | Joe   | Melson | JR    | Hunter | TJ |  |  |  |

| Time     | Casing Pressure   | Tubing Pressure | Bbls. Pumped | Rate  | Service Log  |
|----------|-------------------|-----------------|--------------|-------|--|
| 10:20 AM |                   |                 |              |       | on loc. Discuss Safety, Set-up, Plan job. out of hole, welding scratchers on pipe.   |
| 10:40    |                   |                 |              |       | Start 5/2 csg. Shoe Joint @ 12:03' cent 1-Thru-10' Basket 4+6 Float Shoe + L.O. Baffle on S.I. Tag Bottom @ 3541' Pickup to 3534' CIR + ROTATE CASING. |
| 2:20 PM  | 200 <sup>H</sup>  |                 | 12           | 5     | Pump 12 BBLs super flush   |
|          |                   |                 | 5            | 5     | Pump 5 BBLs H2O  |
|          |                   |                 | 6            | 5     | Mix + Pump 25 SKS 60/40 scavenger @ 14"  |
|          |                   |                 | 5            | 5     | Mix + Pump 130 SKS AA2 cement @ 15"  |
|          |                   |                 | 33           |       | Finish mix washout PLUMP + LINE  |
| 2:45     |                   |                 |              | 6 1/2 | Drop L.O. Plug, Start Disp.  |
|          | 500 <sup>H</sup>  |                 |              | 6     | caught hift PSI w/ 58 BBL out  |
| 3:00     | 1500 <sup>H</sup> |                 | 84           | 4 1/2 | Plug down  |
|          |                   |                 |              |       | Release PSI - "OK"   |
|          |                   |                 | 7            |       | Plug R.H. w/ 30 SKS 60/40 P02  |
|          |                   |                 | 5            |       | Plug M.H. w/ 20 SKS 60/40 P02  |
|          |                   |                 |              |       | washup + Rack up.  |
| 4:30     |                   |                 |              |       | Job complete.  |
|          |                   |                 |              |       | Thanks Allen, Joe, TJ, JR.   |