



BASIC
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET
1718 04489 A

DATE _____ TICKET NO. _____

| | | | | | | | | | |
|---------------------------------------|-----|--|-----|------------|-----|----------------------------|-----------|-------|------|
| DATE OF JOB: 8-23-11 DISTRICT: KANSAS | | NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.: | | | | | | | |
| CUSTOMER: FG Holl Co LLC | | LEASE: Le Rog Farm Trust 1-30 WELL NO.: | | | | | | | |
| ADDRESS: | | COUNTY: Bartol 30-19-14 STATE: KANSAS | | | | | | | |
| CITY: STATE: | | SERVICE CREW: Allen, James, McGraw | | | | | | | |
| AUTHORIZED BY: | | JOB TYPE: 8-5/8" Surface CNU | | | | | | | |
| EQUIPMENT# | HRS | EQUIPMENT# | HRS | EQUIPMENT# | HRS | TRUCK CALLED | DATE | AM/PM | TIME |
| 78443 PU | 1 | | | | | | 8-23-11 | PM | 400 |
| 19889-19842 | 1 | | | | | ARRIVED AT JOB | | PM | 600 |
| 19826-19860 | 1 | | | | | START OPERATION | | AM | 1200 |
| | | | | | | FINISH OPERATION | | AM | 100 |
| | | | | | | RELEASED | | PM | 200 |
| | | | | | | MILES FROM STATION TO WELL | 6.5-miles | | |

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

| ITEM PRICE REF. NO. | MATERIAL, EQUIPMENT AND SERVICES USED | UNIT | QUANTITY | UNIT PRICE | \$ AMOUNT |
|---------------------|---------------------------------------|------|----------|------------|-----------|
| CP101 | A-Cow Blend Common | SK | 200 | | |
| CP100 | Common | SK | 200 | | |
| CC102 | Cell FLAKE | lb | 100 | | |
| CC109 | Calcium Chloride | lb | 1128 | | |
| CC200 | Cement Gel | lb | 376 | | |
| CF105 | Top Rubber cement Plug 8-5/8 | EA | 1 | | |
| CF153 | Cent 8-5/8" Blue | EA | 3 | | |
| E100 | Unit mileage charge Pickup | m. | 65 | | |
| E101 | Heavy Equip mileage | m. | 130 | | |
| E113 | Bulk Delivery Charge | TM | 1222 | | |
| CF201 | Depth Charge 501-1800 | 4-hr | 1 | | |
| CF240 | Blending & mixing service chg | SK | 200 | | |
| CF504 | Plug container & lubrication chg | Job | 1 | | |
| S003 | Service Supervisor Cost 8 hrs @ rate | EA | 1 | | |

SUB T

CHEMICAL / ACID DATA:

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|---------------------|------------|
| SERVICE & EQUIPMENT | %TAX ON \$ |
| MATERIALS | %TAX ON \$ |

SERVICE REPRESENTATIVE: Allen F. West

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: *[Signature]*
(WELL OWNER OPERATOR CONTRAC

FIELD SERVICE ORDER NO.

| | | |
|-----------------------------|--------------------|-------------------------------|
| Customer F G HOLL CO LLC | Lease No. | Date 8-23-11 |
| Lease Le Roy Farm Trust | Well # 1-30 | |
| Field Order # 24489A | Station Pratt | Casing 8-5/8" |
| Type Job 8-5/8" Surface | Depth 850' | County Barton |
| | Formation T0850 | State KS |
| | | Legal Description T0-19-14 |

| PIPE DATA | | PERFORATING DATA | | FLUID USED | | TREATMENT RESUME | | |
|-----------------|--------------|------------------|--------|--------------------|---------------------|------------------|------------------|--|
| Casing Size | Tubing Size | Shots/Ft | | Acid | RATE | PRESS | ISIP | |
| 8-7/8" | | | 200 | SKs A-con @ 12.6 # | | | 5 Min. @ 15 # | |
| Depth 850' | Depth | From | To 200 | Pre Pad SKs common | Max 20% gel / 3% cc | | 10 Min. | |
| Volume 52 | Volume | From | To | Pad | Min | | 15 Min. | |
| Max Press 500 # | Max Press | From | To | Frac | Avg | | Annulus Pressure | |
| Well Connection | Annulus Vol. | From | To | | HHP Used | | Total Load | |
| Plug Depth 830 | Packer Depth | From | To | Flush Disp H2O | Gas Volume | | | |

| | | |
|-------------------------------------|---------------------------|------------------|
| Customer Representative Steve TP | Station Manager Scotty | Treater Allen |
|-------------------------------------|---------------------------|------------------|

| Service Units | 25443 | 19889 | 19842 | 19826 | 19880 | | | | |
|---------------|-------|-------|---------|-------|--------|--|--|--|--|
| Driver Names | Allen | James | Anthony | Mike | McGraw | | | | |

| Time | Casing Pressure | Tubing Pressure | Bbls. Pumped | Rate | Service Log |
|----------|-----------------|-----------------|--------------|------|---|
| 6:00 AM | | | | | Onloc. Discuss Safety, Setup Plan etc |
| 8:33 | | | | | Start back in hole w/ short trip. |
| 10:30 | | | | | Start 8-5/8 casing 24# |
| | | | | | Cent on #1 - #10 - #18 |
| 12:00 PM | | | | | Pipe @ 850' Hook up + CIR. w/Rig. |
| 12:15 | | | | | Hook up to cent well |
| | | | 76 | 5 | Mix 200 SKs A-con Blend @ 12.6 # |
| | | | 48 | 5 | Mix 200 SKs common w/ 2% gel 3% cc, 1/4# cell flake |
| | | | | | Finish mix cent. |
| | | | | | Release Top Rubber Plug. |
| | | | | 5 | Start Disp. |
| 1:00 | | | 52 | 3 | Plug down |
| | | | | | Close in @ well. |
| | | | | | Release PST. |
| | | | | | Wash up Pump Truck. |
| | | | | | Rack up Pump Truck |
| 2:00 | | | | | Job Complete. |
| | | | | | Cement CIR. To Pit |
| | | | | | Thanks Allen James, McGraw |