


Lease:	Burriss	
Owner:	Bobcat Oilfield Services	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 515'Ft 2 7/8" 8Rd	Cemented: 70 Sacks	Hole Size: 5 5/8"



Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056  
Cell # 620-363-2683  
Office # 913-795-2991

Well #: 6-13
Location: SE, SW, SE, SW S12-T17-R24E
County: MIAMI
FSL: 195' FT.
FEL: 3385' FT.
API#: 15-121-296916-00-00
Started: 9-27-13
Completed: 10-01-30

SN: 470' FT.	Packer:	TD: 520' FT.
Plugged:	Bottom Plug:	

## Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOP SOIL	5	507	LIME
5	6	CLAY	2	507	SHALE
47	53	LIME	7	514	LIME
28	101	SHALE	TD	520	SHALE
10	111	LIME			
6	117	SHALE			
13	126	SAND (OIL SHOW) (POOR BLEED)			
16	142	SHALE			
8	150	LIME			
46	196	SHALE			
2	198	LIME			
1	199	SHALE			
5	204	LIME			
15	219	SHALE			
27	246	LIME			
3	249	BLACK SHALE			
5	254	SHALE			
1	255	LIME			
4	259	SHALE			
19	278	LIME			
2	280	BLACK SHALE			
5	285	LIME			
4	289	SHALE			
5	294	LIME			
3	297	SHALE			
8	305	SHALE (LIMEY)			
6	311	SANDY SHALE (ODOR)			
23	334	SHALE			
5	339	SAND (DRY)			
66	405	SHALE			
11	416	SANDY SHALE (SLIGHT OIL SHOW)			
23	439	SHALE			
2	441	BLACK SHALE			
32	473	SHALE			SET SURFACE 2:30 PM - 9-27-13
3	476	OIL SASND (SHALEY) (FAIR BLEED)			CALLED IN 12:30PM - TALKED TO BROOKE
2.5	478.5	SANDY SHALE (SOME OIL SAND STREAK)			WELL TD 520' FT.
1.5	480	OIL SAND (VERY SHALEY) (POOR BLEED)			SET 515' FT. OF 2 7/8" 8 ROUND PIPE - 3:00 PM - 10-01-13
1.5	481.5	OIL SAND (SOME SHALE) FAIR BLEED)			CALLED IN 1:50 PM - TALKED TO BROOKE
7	488.5	BLACK SAND (SOME OIL SHOW) (FAIR GAS SHOW) (SOME WATER)			
4.5	493	BLACK SAND (WATER & SOME GAS)			
9	502	SHALE			



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 6-13
Location: SE,SW,SE,SW, S12,T17,R24E
County: MIAMI
FSL: 195'FT.
FEL: 3385'FT.
API#: 15-121-29616-00-00
Started: 9/27/13
Completed: 10/01/13

Lease :	BURRIS
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

## Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	476	0:00	-----		
1	477	2:30	2.5	SANDY SHALE (SOME OIL SAND STTEAK) (POOR BLEED)	478.5'FT.
2	478	5:30	3		
3	479	8:30	3		
4	480	10:00	1.5	OIL SAND (VERY SHALEY) (POOR BLEED)	480' FT.
5	481	11:00	1	OIL SAND (SOME SHALE ) (FAIR BLEED)	481.5'FT.
6	482	12:00	1	BLACK SAND (SOME OIL SHOW) (FAIR GAS SHOW) (SOME WATER)	488.5'FT.
7	483	13:00	1		
8	484	14:00	1		
9	485	14:30	.5		
10	486	15:30	1		
11	487	16:30	1		
12	488	17:30	1		
13	489	19:00	1.5	BLACK SAND (WATER & SOME GAS)	493'FT.
14	490	20:00	1		
15	491	21:30	1.5		
16	492	23:00	1.5		
17	493	25:00	2	SHALE	
			2		
18	494	27:00	1.5		
19	495	29:30			
20	496	31:00			

RECEIVED BY

X

QUANTITY ORDERED	UNIT	DESCRIPTION	UNITS	PRICE / EA	AMOUNT
280	EA	80# SX FLY ASH	280	5.20 / EA	1,456.00
245	EA	94# PORTLAND CEMENT 1/11	245	9.00 / EA	2,205.00
14	EA	RETURNABLE PALLET	14	15.00 / EA	210.00 *
14	EA	SHRINK WRAPPED PALLET	14	5.00 / EA	70.00
1	EA	FUEL	1	48.55 / EA	48.55

Burns  
6/13

\*\* AMOUNT CHARGED TO STORE ACCOUNT \*\*

INVOICE # 178603  
 TAX: 246.10  
 TOTAL AMOUNT: 4334.65

DEL. DATE: 9/14/13 TERMS: 1  
 SLIP: RR ROBERT ROAD  
 TAX: 001 LOUISIANA, MS  
 ORDER 75805

28714 E. LINN RD.  
 LEBLANC, LA 70339

MOSSMAN LUMBER  
 2725 METCAL RD.  
 LOUISIANA, MS 39053

CUSTOMER NO.	FOR NO. PURCHASE ORDER NO.	REFERENCE	NET 100%	CLERK	DATE	TIME
					10/27/13	7:58

True Value

PAGE NO 1

**MOSSMAN LUMBER COMPANY**  
 1/2 Mile North of Louisiana  
 2725 Metcal Rd.  
 P.O. Box 728  
 Louisiana, Kansas 66053  
 813-837-2955 • 1-800-521-1764