


Lease:	Anderson	
Owner:	Bobcat Oilfield Services Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 83/4"
Longstring: 665' FT 2/78" 8RD	Cemented: 80 Sacks Cement	Hole Size: 5 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 3W-13
Location: ^{NE} SW,SW,SW,SW S32-T16-R22
County: MIAMI
FSL: 660'FT
FEL: 4950'FT
API#: 15-121-29645-00-00
Started: 10/09/13
Completed: 10/10/13

SN: NONE	Packer: NONE	TD: 670' FT.
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	TOP SOIL	3	458	LIGHT SHALE (LIME STREAK)
2	4	CLAY	3	461	GAS SAND (SOME SHALE) (SLIGHT OIL SHOW)
8	12	LIME	2	463	OIL SAND (SOME SHALE) (FAIR BLEED)
3	15	SHALE	17	480	SHALE
17	32	LIME	1	481	BLACK SHALE
2	34	SHALE	10	491	LIGHT SHALE
2	36	RED BED	28	519	SHALE (LIMEY)
12	48	SHALE	7	526	LIME
6	54	SANDY SHALE	7	533	SHALE
14	68	LIME	2	535	LIME
18	86	SHALE	6	541	SHALE
5	91	SANDY SHALE	10	551	DARK SHALE (COAL STREAK)
7	98	SAND (DRY)	7	558	SHALE
65	163	SHALE	8	566	LIME
17	180	LIME	2	568	SANDY SHALE
10	190	SHALE	7	575	SHALE
7	197	SAND (SHALEY) (DRY)	5	580	SHALE (LIMEY)
12	209	SHALE	3	583	LIME
4	213	LIME	3	586	BLACK SHALE
36	249	SHALE	2	588	SHALE
14	263	LIME	13	601	LIME (SHALEY)
15	278	SHALE	12	613	SHALE (LIME STREAK)
11	289	LIME	3	616	LIME (SHALEU)
2	291	SHALE	6	622	BLACK SHALE
13	304	LIME	3	625	SHALE
3	307	SHALE	1	626	LIME
4	311	BLACK SHALE	6	632	SHALE
22	333	LIME	1	633	LIGHT SHALE (OIL SAND STREAK)
2	335	SHALE	1	634	OIL SAND (SOME SHALE) (FAIR BLEED)
2	337	BLACK SHALE	2.5	363.5	OIL SAND (SHALEY) (FAIR BLEED)
6	343	LIME	2	638.5	OIL SAND (SOME SHALE) (FAIR BLEED)
3	346	SHALE	1.5	640	OIL SAND (SHALEY) (FAIR BLEED)
5	351	LIME	10	650	SANDY SHALE
1	352	BLACK SHALE	TD	670	SHALE
4	356	SHALE			
5	361	SHALE (LIMEY)			
13	374	SHALE			SURFACE SET 5:30 PM ON 10/09/2013
10	384	SANDY SHALE (DRY SAND STRIPS)			CALLED IN 3:20 PM – TALKED TO JUDY
3	387	OIL SAND (SHALEY) (FAIR BLEED)			WELL TD 680'FT.
6	393	SANDY SHALE			SET 665'FT. OF 2 7/8" 8 ROUND PIPE – 4:30 PM – 10/10/2013
62	455	SHALE			CALLED IN 3:30 PM – TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 3W-13 <i>NE</i>
Location: SW,SW,SW,SW, S32-T16-R22E
County: MIAMI
FSL: 660'FT.
FEL: 4950'FT.
API#: 15-121-29645-00-00
Started: 10/09/13
Completed: 10/10/13

Lease :	ANDERSON
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	634	0:00	-----	OIL SAND (SHALEY) (FAIR BLEED)	636.5'FT.
1	635	2:00	2		
2	636	4:00	2		
3	637	5:30	1.5	OIL SAND (SOME SHALE) (FAIR BLEED)	638.5'FT.
4	638	7:00	1.5		
5	639	8:30	1.5	OIL SAND (SHALEY) (FAIR BLEED)	640'FT.
6	640	10:30	2		
7	641	13:30	3	SANDY SHALE	
8	642	17:30	4		
9	643	21:30	4		
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

RECEIVED BY

X

POINT CHARGED TO STATE ACCOUNT # 4.334.85

TOTAL TAX 246.10
 TAX CHARGE 4334.65
 TOTAL 4580.75
 TAX CHARGE 4334.65
 TAX TOTAL 246.10
 TAX TOTAL 4580.75

QUANTITY	ORDERED	UNIT	DESCRIPTION	UNITS	PRICE PER UNIT	EXTENSION
280	1	EA	80# SX FLY NSH	280	5.20 /EA	1,456.00
245	1	EA	94# PORTLAND CEMENT 1/11	245	9.00 /EA	2,205.00
14	1	EA	RETURNABLE PALLET	14	15.00 /EA	210.00
14	1	EA	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL SURCHARGE	1	48.55 /EA	48.55

Anderson SW-13

DOC# 176603
 * INVOICE *
 RR ROBERT ROAD
 001 LOUISIANS, KS
 DEL. DATE: 9/14/13 TERMS: 51
 ORDER 75605

128774 E. LINN RD.
 TROY, MO

PORTLAND CEMENT
 94# 5052

CUSTOMER NO.	KRM NO.	PURCHASE ORDER NO.	WEIGHTS	NET WT	DATE	TIME
					10/27/13	7:25

True Value.

PAGE NO 1

MOSSMAN LUMBER COMPANY
 1/2 Mile North of Louisa
 2725 Market Rd.
 P.O. Box 728
 Louisa, Kansas 66053
 813-837-2955 • 1-800-521-1764

