


Lease:	Anderson	
Owner:	Bobcat Oilfield Services, Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 665' 2 7/8 8 RD PIPE	Cemented: 80 Sacks of Cement	Hole Size: 5 5/8"



Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056  
Cell # 620-363-2683  
Office # 913-795-2991

Well #: 2W-13
Location: S2, S2, SW, SW: S32-T16-R22E
County: MIAMI
FSL: 270' FT.
FEL: 4620' FT.
API#: 15-121-29644-00-00
Started: 10-11-2013
Completed: 10-14-2013
TD: 670' FT.

SN: NONE	Packer: NONE
Plugged:	Bottom Plug:

## Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	TOP SOIL	25	518	SHALE (LIMEY)
6	8	CLAY	7	525	LIME
8	16	SHALE	7	532	SHALE
32	48	LIME	2	534	LIME
5	53	SHALE	19	553	SHALE
14	67	LIME	1	554	COAL
24	91	SHALE	3	557	SHALE
5	96	SAND (DRY)	9	566	LIME (SHALEY)
65	161	SHALE	12	578	DARK SHALE
18	179	LIME	5	583	LIME
7	186	SHALE	3	586	COAL
9	195	SAND (DRY)	2	588	SHALE
12	207	SHALE	7	595	DARK SHALE (LIMEY)
4	211	LIME	4	599	LIME (SHALEY)
37	248	SHALE	22	621	SHALE (LIMEY)
12	260	LIME	2	623	BLACK SHALE
17	277	SHALE	3	626	SHALEY (LIMEY)
11	288	LIME	2	628	LIME
2	290	SHALE	5	633	SHALE
13	303	LIME	1	634	LIGHT SANDY SHALE
2	305	SHALE	1	635	SHALE (OIL SAND STREAK)
2	307	BLACK SHALE	1.5	636.5	OIL SAND (SOME SHALE) (FAIR BLEED)
25	332	LIME	.5	637	SANDY SHALE
4	336	BLACK SHALE	1	638	OIL SAND (SHALEY) (FAIR BLEED)
4	340	LIME	.5	638.5	SANDY SHALE
4	344	SHALE	2	640.5	OIL SAND (SHALEY) (FAIR BLEED)
5	349	LIME	6.5	647	SANDY SHALE
1	350	BLACK SHALE	TD	670	SHALE
3	353	SHALE			
8	361	SHALE (LIMEY)			
9	370	SHALE			
11	381	SANDY SHALE (SLIGHT OIL SHOW)			
5	386	SAND (SLIGHT OIL SHOW)			SET SURFACE 5:30 PM – 10/11/13
14	400	SANDY SHALE			CALLED IN 3:20 PM – TALKED TO BROOKE
56	456	SHALE			WELL TD 670' FT.
1	457	SANDY SHALE (ODOR)			LONGSTRING SET 665' FT. OF 2 7/8" 8 RD PIPE – 4:30 PM – 10/14/13
4	461	OIL SAND (SOME SHALE) (POOR BLEED)			CALLED IN 3:20 PM – TALKED TO BROOKE
1	462	OIL SAND (SOME SHALE) (FAIR BLEED)			
18	480	SHALE			
1	481	BLACK SHALE			
12	493	SHALE			



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 2W-13
Location: S2,S2,SW,SW, - S32,T16,R22E
County: MIAMI
FSL: 270'FT.
FEL: 4620'FT.
API#: 15-121-29644-00-00
Started: 10/11/13
Completed: 10/14/13

Lease :	ANDERSON
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

# Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	636	0:00	-----	OIL SAND (SOME SHALE) (FAIR BLEED)	636.5'FT.
1	637	2:00	2	SANDY SHALE	637'FT.
2	638	4:00	2	OIL SAND (SHALEY) (FAIR BLEED)	638'FT
				SANDY SHALE	638.5'FT.
3	639	6:30	2.5		
4	640	8:00	1.5	OIL SAND (SHALEY) (FAIR BLEED)	640.5'FT.
5	641	11:00	3	SANDY SHALE	
6	642	14:00	3		
7	643	17:00	3		
8	644	21:00	4		
9	645	25:00	4		
10	646				
11	647				
12					
13					
14					
15					
16					
17					
18					
19					
20					



1/2 Mile North of Loulsburg  
27295 Metcalf Rd.  
P.O. Box 729  
Loulsburg, Kansas 66053  
913-837-2956 • 1-800-521-1764

# MOSSMAN LUMBER COMPANY

PAGE NO 1

*True Value.*

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
151			ORDER # 76254	NET 10TH	RR	10/18/13	2:34

DELIVERY: 11:20 AM - 1:00 PM FRIDAY  
 DEL. DATE: 10/16/13 TERM#551  
 SLSPR: RR ROBERT ROND  
 TAX: 001 LOUISBURG, KS  
 DOC# 176697  
 \*\*\*\*\*  
 \* INVOICE \*  
 \*\*\*\*\*  
 ORDER 76254

QUANTITY SHIPPED	QUANTITY ORDERED	UNIT	SKU	DESCRIPTION	UNITS	PRICE/PER	EXTENSION
160		EA	FLYASH	80# SX FLY ASH	160	5.20 /EA	832.00
350		EA	PORTLAND	94# PORTLAND CEMENT 1/TT	350	9.00 /EA	3,150.00
14		EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14		EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL	FUEL SURCHARGE	1	48.55 /EA	48.55

*Anderson  
2W-13*

** AMOUNT CHARGED TO STORE ACCOUNT **	4,683.41	TAXABLE	4310.55
		NON-TAXABLE	0.00
		SUBTOTAL	4310.55
		TAX AMOUNT	372.86
		TOTAL DUE	4683.41

X RECEIVED BY \_\_\_\_\_

MOSSMAN LUMBER 91303/26/1