


Lease:	Anderson	
Owner:	Bobcat Oilfield Services, Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 ¼"
Longstring: 659' 2 7/8 8 RD PIPE	Cemented: 80 Sacks of Cement	Hole Size: 5 5/8"



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: 4-13
Location: NE, SW, SW, SW: S32-T16-R22
County: MIAMI
FSL: 495' FT.
FEL: 4785' FT.
API#: 15-121-29640-00-00
Started: 10-15-2013
Completed: 10-16-2013

SN: 630' FT.	Packer: NONE
Plugged:	Bottom Plug:

TD: 661' FT.

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	TOP SOIL	16	516	SHALE
3	5	CLAY	7	523	LIME
5	10	SHALE	7	530	SHALE
25	35	LIME	2	532	LIME
2	37	SHALE	12	544	SHALE
13	50	SAND (DRY)	7	551	DARK SHALE
15	65	LIME	1	552	COAL
24	89	SHALE	3	555	SHALE
4	93	SAND (DRY)	6	561	LIME (SHALEY)
67	159	SHALE	17	578	SHALE
18	177	LIME	3	581	LIME
14	191	SHALE	4	585	BLACK SHALE
5	196	SAND (DRY)	8	593	SHALE (LIMEY)
15	211	SHALE	5	598	LIME (SHALEY)
3	214	LIME	13	611	SHALE (LIMEY)
32	246	SHALE	4	615	LIME
15	261	LIME	4	619	DARK SHALE
14	275	SHALE	1	620	BLACK SHALE
12	287	LIME	3	623	SHALE (LIMEY)
2	289	SHALE	3	626	LIME (SHALEY)
14	303	LIME	5	631	LIGHT SHALE
2	305	SHALE	1	632	SANDY SHALE (OIL SAND STREAK) (POOR BLEED)
2	307	BLACK SHALE	1	633	OIL SAND (SOME SHALE) (FAIR BLEED)
24	331	LIME	2	635	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)
2	333	SHALE	5	640	OIL SAND (SOME SHALE) (FAIR BLEED)
2	335	BLACK SHALE	11	651	SANDY SHALE
5	340	LIME	TD	661	SHALE
4	344	SHALE			
5	349	LIME			
1	350	BLACK SHALE			
26	376	SHALE			
7	383	SANDY SHALE			SET SURFACE CASING - 5:30 PM - 10/15/13
4	387	SAND (SOME SHALE) (OIL SHOW)			CALLED IN 11:00 AM - 10/16/13
9	396	SANDY SHALE			WELL TD 661' FT.
58	454	SHALE			SET LONGSTRING: 659' FT. OF 27/8" 8RD PIPE - 4:00 PM - 10/16/13
2	456	LIGHT SHALE (LIMEY)			CALLED IN 3:00 PM - TALKED TO BROOKE
5	461	OIL SAND (SHALEY) (FAIR BLEED)			
18	479	SHALE			
1	480	COAL			
10	490	SHALE			
10	500	SHALE (LIMEY)			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4-13
Location: NE,SW,SW,SW, - S32,T16,R22E
County: MIAMI
FSL: 495'FT.
FEL: 4785'FT.
API#: 15-121-29640-00-00
Started: 10/15/13
Completed: 10/16/13

Lease :	ANDERSON
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	632	0:00	-----	OIL SAND (SOME SHALE) (FAIR BLEED)	633'FT.
1	633	1:30	1.5		
2	634	4:30	3	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	635'FT.
3	635	8:30	4		
4	636	10:30	2	OIL SAND (SOME SHALE) (FAIR BLEED)	640'FT.
5	637	11:30	1		
6	638	12:30	1		
7	639	15:00	2.5		
8	640	17:00	2	SANDY SHALE	
9	641	22:00	5		
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					



MOSSMAN LUMBER COMPANY

1/2 Mile North of Louisburg
27295 Metcalf Rd.
P.O. Box 729
Louisburg, Kansas 66053
913-837-2955 • 1-800-521-1764

PAGE NO 1

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
151			ORDER # 76254	NET 10TH	RR	10/18/13	2:34

ALBERT OIL
2805 CRAWFORD ROAD
LOUISBURG, KS 66053

287TH & TROY ROAD
FRIDAY

DEL. DATE: 10/16/13 TERMS51
SLSPR: RR ROBERT RAND
TAX : 001 LOUISBURG, KS

DOC# 178697

* INVOICE *

ORDR 76254

QUANTITY	UNIT	SKU	DESCRIPTION	UNITS	PRICE/PER	EXTENSION
160	EA	FLYASH	80# SX FLY ASH	160	5.20 /EA	832.00
350	EA	PORTLAND	94# PORTLAND CEMENT 1/TT	350	9.00 /EA	3,150.00
14	EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14	EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1	EA	FUEL	FUEL SURCHARGE	1	48.55 /EA	48.55

*Anderson
413*

*E. AMOUNT CHARGED TO STORE ACCOUNT * 4,683.41
TAXABLE 4310.55
NON-TAXABLE 0.00
SUBTOTAL 4310.55

RECEIVED BY

TAX AMOUNT 372.86
TOTAL DUE 4683.41

P.1
MOSSMAN LUMBER 913037297