



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 41738 ✓
LOCATION Eureka
FOREMAN Ross McCoy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT API #15-001-30669 ✓

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5/28/13	1828	Kirk # KD-6	9	24	18E	Allen
CUSTOMER <u>Colt Energy, Inc</u>						
MAILING ADDRESS <u>P.O. Box 388</u>						
CITY <u>Iola</u>	STATE <u>KS</u>	ZIP CODE				
			TRUCK #	DRIVER	TRUCK #	DRIVER
			<u>520</u>	<u>John</u>		
			<u>502</u>	<u>Steve (elder)</u>		

JOB TYPE L/S 0 HOLE SIZE 6 3/4" HOLE DEPTH 930' CASING SIZE & WEIGHT 4 1/2" 10 1/2 #/ft.
CASING DEPTH 921.65' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 13.6# SLURRY VOL 33 Bbl WATER gal/sk 6.5 CEMENT LEFT in CASING 21'
DISPLACEMENT 14.6 Bbl DISPLACEMENT PSI 500# ~~PSI~~ Shut in @ 500 PSI RATE _____

REMARKS: Safety meeting. Rig up to 4 1/2" casing. Break circulation w/ fresh water. Mixed 150# gel-flush, 5 Bbl water spacer. Mixed 135 sacks class A cement w/ 2% gel, 1% cacl2 & 1# phenoseal/sk @ 13.6# /gal washout pump & lines, release plug. Displace w/ 14.6 Bbl fresh water. Final pump pressure 500 PSI. Shut casing in @ 500 PSI. Good cement returns to surface = 6 Bbl slurry to pit. Job complete. Rig down.

" Thank You "

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	1085.00	1085.00
5406	50	MILEAGE	4.20	210.00
11045	135 sacks	Class A cement	15.70	2119.50
1118B	255#	2% gel	.22	56.10
1102	130#	1% cacl2	.78	101.40
1107A	135#	1# phenoseal/sk	1.35	182.25
1118A	150#	gel-flush	.22	33.00
5407A	6.35	ten mileage bulk truck	7.41	477.68
4404	1	4 1/2" top rubber plug	47.25	47.25
			Subtotal	4292.18
			7.55% SALES TAX	191.74
			ESTIMATED TOTAL	4473.92

Ravin 3737

AUTHORIZATION R.R. [Signature]

TITLE [Signature]

DATE 5/28/2013

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.