



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.  
P.O. Box 129  
Liberal, Kansas 67905  
Phone 620-624-2277

FIELD SERVICE TICKET

1717 01959 A

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

DATE OF JOB <b>8-20-11</b>	DISTRICT <b>1717</b>	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:
CUSTOMER <b>Oxy USA</b>	LEASE <b>Wilson 'F'</b>						WELL NO. <b>1</b>
ADDRESS		COUNTY <b>Haskell</b>			STATE <b>Ks</b>		
CITY STATE		SERVICE CREW <b>Cochran/Mendoza</b>					
AUTHORIZED BY <b>T. Davis</b>		JOB TYPE: <b>Z42 8 5/8 Surface</b>					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE AM TIME
<b>21755</b>	<b>5.25</b>	<b>19828</b>	<b>5.25</b>				<b>8-20 AM 12:00</b>
<b>27808</b>	<b>5.25</b>	<b>19883</b>	<b>5.25</b>			ARRIVED AT JOB	<b>8-20 AM 13:45</b>
<b>19553</b>	<b>5.25</b>	<b>19829</b>	<b>5.25</b>			START OPERATION	<b>8-20 AM 16:20</b>
		<b>19566</b>	<b>5.25</b>			FINISH OPERATION	<b>8-20 AM 17:40</b>
						RELEASED	<b>8-20 AM 19:00</b>
						MILES FROM STATION TO WELL	<b>33</b>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: *Andy Saldy*  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	'A-con' Blend	sk	390		
CL110	Premium Plus	sk	450		
CC109	Calcium Chloride	lb	380		
CC102	Cello flake	lb	30		
CC130	C-51	lb	74		
CF1203	Auto fill float shoe	ea	1		
CF1363	" " " " collar	ea	1		
CF1773	Centralizer	ea	1		
CF1903	Basket	ea	1		
CF503	Stey Ring	ea	1		
CF105	Top Plug	ea	1		
E101	Heavy Equip. Mileage	mi	90		
CE240	Bleeding + Mixing Serv. Chrg.	sk	540		
E113	Bulk Delivery	tm	72		
CE202	Depth Chrg. 1001-2000'	4hr	1		
CE504	Plug Container	job	1		
E100	Pick-up Mileage	mi	30		
5003	Service Supervisor	ea	1		
T105	Cement Data Acquisition Monitor	ea	1		
SUB TOTAL					17830.47

  

CHEMICAL / ACID DATA:			

  

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE: *Mike Coch* THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: *Andy Saldy*  
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



# Cement Report

Customer <i>Oxy USA</i>		Lease No.		Date <i>8-20-11</i>	
Lease <i>Wilson "F"</i>		Well # <i>1</i>		Service Receipt <i>1717 01959</i>	
Casing <i>8 5/8</i>	Depth	County <i>Haskell</i>	State <i>Ks</i>		
Job Type <i>Z 42 Subsec</i>	Formation	Legal Description <i>23 30 33</i>			
<b>Pipe Data</b>			<b>Perforating Data</b>		<b>Cement Data</b>
Casing size	Tubing Size	<b>Shots/Ft</b>		<b>Lead</b>	
Depth	Depth	From	To	<i>See Call Sheet</i>	
Volume	Volume	From	To		
Max Press	Max Press	From	To		
Well Connection	Annulus Vol.	From	To		
Plug Depth	Packer Depth	From	To	<b>Tail in</b>	
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>17:45</i>					<i>On Loc. / Held Safety Meeting</i>
					<i>Rig Running Csg.</i>
<i>15:15</i>					<i>Csg on Bottom Cir. w/ Rig</i>
<i>16:15</i>	<i>2500</i>				<i>Test Pump + Lines</i>
<i>16:20</i>	<i>400</i>		<i>167</i>	<i>5.5</i>	<i>Start Lead Cmt 390sk @ 12.1"</i>
<i>16:48</i>	<i>300</i>		<i>36</i>	<i>3</i>	<i>Start Tail Cmt 150sk @ 14.8"</i>
<i>16:59</i>					<i>Shutdown + Drop Plug</i>
<i>17:01</i>	<i>250</i>		<i>0</i>	<i>5</i>	<i>Start Disp. w/ fresh H<sub>2</sub>O</i>
<i>17:20</i>	<i>250</i>		<i>102</i>	<i>2.5</i>	<i>Slow Rate</i>
<i>17:24</i>	<i>1350</i>		<i>112</i>	<i>2.5</i>	<i>Bump Plug</i>
<i>17:32</i>	<i>0</i>		<i>112</i>	<i>0</i>	<i>Release / float Held</i>
<i>17:35</i>					<i>End Job</i>
					<i>Circulated CMT to the Pit</i>
	<i>800</i>				<i>Pressure before Plug landed</i>
					<i>Total Pipe 1809.63 SJ 44.77</i>
					<i>TD 1805</i>
Service Units	<i>21755</i>	<i>2790919553</i>	<i>1982919883</i>	<i>1982719566</i>	
Driver Names	<i>Cocharn</i>	<i>Mendoza</i>	<i>Orriz</i>	<i>Siroky</i>	

Andy  
Customer Representative

J. Bennett  
Station Manager

M. Cocharn  
Cementer