



BASIC
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET
1718 05252 A

DATE _____ TICKET NO. _____

DATE OF JOB 10-25-11		DISTRICT KANSAS		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/>		PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/>		CUSTOMER ORDER NO.:	
CUSTOMER FG Holl Co. LLC				LEASE REECE #1-32				WELL NO.	
ADDRESS				COUNTY Hodgeman		STATE KANSAS		32-22-21	
CITY				STATE		SERVICE CREW Allen, T.J. Steve Young			
AUTHORIZED BY				JOB TYPE: 5 1/2" L.S. CNW					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
28443	3 1/2						10-25-11	PM	9:20
33708-20920	3 1/2					ARRIVED AT JOB	10-25-11	AM	1:00
19826-19860	3 1/2					START OPERATION	10-25-11	AM	7:30
						FINISH OPERATION	10-25-11	AM	11:00
						RELEASED	10-25-11	AM	12:00
						MILES FROM STATION TO WELL	90-miles		

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP105	AA-2 cement	SK	150		
CP103	60/40 Poz	SK	50		
CC102	cell FLAKE	lb	38		
CC105	Defoamer Powder	lb	35		
CC111	SALT Fine	lb	672		
CC115	GAS-Blok	lb	141		
CC129	FIA-322	lb	141		
CC201	Gilsonite	lb	1875		
CF607	Latch down Plug + Baffle 5/2	EA	1		
CF1251	Auto Fill Float Shoe 5/2 Blue	EA	1		
CF1651	Turbolizer 5/2 Blue	EA	8		
CF1901	5/2 Basket Blue	EA	1		
CF2002	Cement scratchers Rotating Type	EA	30		
CC154	super flush	gal	500		

SUB TOTAL

PLS

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE *Allen F. Ward*

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: *[Signature]*

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.

Customer FGHoll Co LLC	Lease No.	Date 10-25-11	
Lease REECE	Well # H 1-32	Field Order # 05252A	Station Pratt KS
Type Job 5 1/2" Long string	Casing 5 1/2"	Depth 4563'	County Hodgeman
	Formation CWW	LTD 4580, LTD 4583	State KS
		Legal Description 22-22-21	

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size 5 1/2"	Tubing Size	Shots/Ft	255 SKs	Acid 60/40 Poz	RATE 5 SCAVENGER	PRESS 13.5	ISIP 13.5 gal	
Depth 4563'	Depth	From	To	Pre Pad 150 SKs AA-2 @	Max 15.5 gal		5 Min.	
Volume 108 1/2	Volume	From	To	Pad 12 BBL super Flush	Min		10 Min.	
Max Press 1200	Max Press	From	To	Frac 30 SKs 60/40 Poz	Avg RH		15 Min.	
Well Connection PC	Annulus Vol.	From	To	Flush 205 SKs 60/40 Poz MH	HHP Used		Annulus Pressure	
Plug Depth 4523'	Packer Depth	From	To	Flush Disp H2O	Gas Volume		Total Load	

Customer Representative Rob Long	Station Manager scotty	Treater Allen
-------------------------------------	---------------------------	------------------

Service Units	28433	3370x	20920	19826	19860
Driver Names	Allen TJ	Gibson	Steve	Young	

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Notes
10:00 pm					O+S casing Service Log Duke #5 on loc. Discuss Safety, Setup Plan Job Laying Drill Pipe.
4:15					out of Hole w/ Bit Rig up to Run 5 1/2" casing 15.5#/ft + lay down Kelly
5:25					Start 5 1/2" casing. Shoe Jt. 9.67' w/ Shoe Float + L.D. Baffle in collar.
7:50					cent-1-Thru-8 - Basket 4" in Tag TD Pickup + CIR + Rotate @ 4563' "Good" CIR
10:00	200#		5	5	Pump 5 BBLs H2O spacer
			5	5	Pump 12 BBL super flush
			5	5	Pump 5 BBL H2O spacer
			7	5	mix 25 SKs 60/40 Poz - SCAVENGER @ 13#
			5	5	mix 150 SKs AA-2 cmt @ 15#
			38		Finish mix wash out Pump + Line.
10:23	500#			6	Drop L.D. Plug + Start Disp.
	1500#			5 1/2	caught Lift PSI w/ 82 BBLs out
10:45			108 1/2	4	Plug Down
					Release to TRK OK
11:00			7		Plug RH w/ 30 SKs 60/40
			5		Plug MH w/ 20 SKs 60/40
12:00					wash up + RACK UP. Job complete