



CONSOLIDATED
Oil Well Services, LLC

LaFontaine
Waterflow
ENTERED

TICKET NUMBER 31641
LOCATION Eureka
FOREMAN Russell mcloy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

API 15-20527974

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-27-2011	4758	Metzger 15 R 34 w/w	34	30	14	Wilson
CUSTOMER <u>LAYNE Energy</u>			Gus Jones			
MAILING ADDRESS <u>P.O. Box 160</u>			TRUCK # DRIVER TRUCK # DRIVER			
CITY <u>Sylamore</u>			445 Cliff			
STATE <u>Ks</u>			611 Dan			
ZIP CODE						

JOB TYPE Longstring O HOLE SIZE 6 3/4 HOLE DEPTH 1235 CASING SIZE & WEIGHT 4 1/2 10.5 #
 CASING DEPTH 1252 DRILL PIPE TUBING OTHER
 SLURRY WEIGHT 13.4 SLURRY VOL 44 861 WATER gal/sk 8.0 CEMENT LEFT in CASING 0
 DISPLACEMENT 20 861 DISPLACEMENT PSI 750 MIX POT Bump Plug 1200 RATE 0

REMARKS: Safety meeting, Rig up 4 1/2 casing, Break circulation w/ 25 861 water wash down 3 ft of fill up. Mix 10 sks gel flush w/ hulls 20 861 water SPACER 15 861 caustic soda pre flush. 10 861 D/E water. Mix 135 sks Thickset cement w/ 8" Kolseal 1/8" Phenoseal 1/4" CFL 115 at 13.4 per/gallon wash out Pump + lines shut down, Release latch down plug, Displace w/ 20 861 fresh water. Final Pump PSE 750" Bump Plug to 1250" check float, float held. Good cement returns to surface = 8 861 slurry. Annulus stayed full job complete
 Tear Down. Thank You
Russell

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	975.00	975.00
5406	40	MILEAGE	4.00	160.00
1126 A	135 sks	Thickset cement	18.30	2470.50
1110 A	1080 #	8" Kolseal per/sk	.44	475.20
1107 A	17 #	1/8" Phenoseal per/sk	1.22	20.74
1135 A	34 #	1/4" CFL -115	9.95	338.30
1110 B	500 #	gel flush ahead	.20	100.00
1105	50 #	hulls	.42	21.00
1103	100 #	caustic soda	1.52	152.00
5407A	7.43	Tow mileage Bulk Truck	1.26	374.47
4453	1	4 1/2 hatch down plug	155.00	155.00
4156	1	4 1/2 Flapper Type float shoe	175.00	175.00
				5,417.21
			SALES TAX	246.20
			ESTIMATED TOTAL	5,663.41

Ravin 3737

AUTHORIZATION *Jay Mark* TITLE *Drilling foreman* DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.