



CONSOLIDATED
Oil Well Services, LLC



ENTERED

TICKET NUMBER 31627
LOCATION Eureka, KS
FOREMAN Shannon Felk

FIELD TICKET & TREATMENT REPORT

CEMENT API # 15-205-27972

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-30-11	4158	metzger 16M-34 WIW	34	30S	14 E	Wilson
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Layne Energy			520	Allen B		
MAILING ADDRESS			611	Chris B		
P.O. Box 160						
CITY	STATE	ZIP CODE				
Sycamore	KS					

JOB TYPE Longstring oil HOLE SIZE 6 3/4 HOLE DEPTH 1287 CASING SIZE & WEIGHT 4 1/2 @ 10.50
CASING DEPTH 1278 DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 13.2-13.4 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 0
DISPLACEMENT 20.5 DISPLACEMENT PSI 700 MIX PSI Plug to 1200 RATE 5BPM
REMARKS: Rig up to 4 1/2" casing Break circulation with 25 Bbl water, mixed 500# gel flush with hull, 25 Bbl water spacer, 15 Bbl caustic soda, 10 Bbl dye water, mixed 135 SKS Thickset cement with 8# Kol-seal/sk 1/8# Phenoseal/sk & 1/4% CFL-115 @ 13.2-13.4 #/gal, wash out pump & lines. Displace with 20.5 Bbl water, with a final pumping pressure of 700 psi, bumped plug to 1200 psi. Good circulation @ all times 6 Bbl slurry to pit. Job complete

"Thanks Shannon & crew"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	975.00	975.00
5406	40	MILEAGE	4.00	160.00
1126 A	135 SKS	Thickset cement	18.30	2470.50
1110 A	1080 #	8# Kol-seal/sk	.44	475.20
1107 A	17 #	1/8# Phenoseal/sk	1.22	20.74
1135 A	34 #	1/4% CFL-115	9.95	338.30
1118 B	500 #	gel flush	.20	100.00
1105	50 #	Hulls	.42	21.00
1103	100 #	Caustic Soda	1.52	152.00
5407 A	7.43	Ton mileage bulk truck	1.26	374.47
4453	1	4 1/2 Latch down Plug	155.00	155.00
4156	1	4 1/2 Flapper Type Float Shoe	175.00	175.00
		Sub Total		5417.21
		SALES TAX 6.3%		246.20
		ESTIMATED TOTAL		5663.41

Ravin 3737

AUTHORIZATION [Signature]

TITLE [Signature]

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form