



**CONSOLIDATED**  
Oil Well Services, LLC

**ENTERED**

TICKET NUMBER 42970 X  
LOCATION Eureka KS  
FOREMAN Shannon Feck

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT 15-001-30699** ✓

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6/25/13	1828	Bowles # BR-2	8	24	18E	Allen
CUSTOMER Colt Energy Inc			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS P.O. Box 388			<del>520</del>			
CITY Iola			520	John S		
STATE KS			479	Colby n		
ZIP CODE			667	Chris B		

JOB TYPE 4/5 HOLE SIZE 7 7/8" HOLE DEPTH 1160 CASING SIZE & WEIGHT 4 1/2, 10.5 #/ft  
CASING DEPTH 1142.10 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT 13.6 # SLURRY VOL \_\_\_\_\_ WATER gal/sk 6.5 CEMENT LEFT in CASING 4' shoe joint  
DISPLACEMENT 18.2 Bbl DISPLACEMENT PSI 400 MIX PSI Bump Plug @ 800 RATE 5 BPM

REMARKS: Rig up to 4 1/2" casing, Break circulation w/ 50 Bbl H2O, mixed 400# gel flush w/ 2 SKS hulls, Brought gel & hulls to surface, 8 Bbl dye H2O. Mixed 200 SKS Class "A" cement w/ 2% gel, 1% calcium & 2 # phenoseal/sk @ 13.6 #/gal. Shut down wash out pump & lines, displace w/ 18.2 Bbl H2O. Final pumping pressure of 400 psi, bumped plug @ 800 psi. Plug & float held, good circulation @ all times, 8-10 Bbl Slurry to pit. Job Complete!

"Thanks Shannon & Crew"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	1085.00	1085.00
5406	50	MILEAGE	4.20	210.00
1104S	200 SKS	Class "A" cement	15.70	3140.00
1118B	380 #	Gel @ 2%	.22	83.60
1102	190 #	Calcium @ 1%	.78	148.20
1107A	400 #	Phenoseal @ 2 #/sk	1.35	540.00
1118B	400 #	Gel Flush	.22	88.00
1105	100 #	Cottonseed hulls	.46	46.00
5407A	9.4 Tons	Ton mileage bulk Truck	1.41	662.70
4408	1	4 1/2" Rubber Plug	47.25	47.25
			Sub Total	6050.75
			SALES TAX 7.55%	309.02
			ESTIMATED TOTAL	6359.77

Ravin 3737

060064

AUTHORIZATION R. R. Adlak TITLE \_\_\_\_\_ DATE 6/25/2013

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.