

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056



Cell # 620-363-2683

Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 626' 2 7/8 8 RD PIPE	Cemented: 75 Sacks of Cement	Hole Size: 5 5/8"
SN: 594'FT.	Packer: NONE	TD: 761' FT.
Plugged: 12 SACKS	Bottom Plug: 761'FT. TO 640'FT.	
Lease:	Boyscout	
Owner:	Bobcat Oilfield Services, Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	

Well #: K3-13
Location: NE, NW, NE, NW: S14-T17- R21E
County: MIAMI
FSL: 5115' FT.
FEL: 3465' FT. 3412
API#: 15-121-29707-00-00
Started: 12-03-2013
Completed: 12-05-2013

Log

Well

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
30	30	CLAY	6	584	BLACK SHALE
17	47	SAND (DRY)	4	588	LIME
72	119	SHALE	6	594	SHALE
19	138	LIME	1	595	OIL SAND (SOME SHALE) (GOOD BLEED)
27	165	SHALE	4	599	OIL SAND (GOOD BLEED)
5	170	LIME	1	600	OIL SAND (SHALEY) (GOOD BLEED)
21	191	SHALE	4	604	SHALE (OIL SAND STREAK)
1	192	RED BED	49	653	SHALE
13	205	SHALE	6	659	DARK SHALE (LIMEY)
16	221	LIME	5	664	DARK SHALE
12	233	SHALE	5	669	SANDY SHALE (ODOR)
29	262	LIME	2	671	SANDY SHALE
3	265	SHALE	10	681	SHALE
4	269	BLACK SHALE	5	686	SANDY SHALE
22	291	LIME	14	700	SANDY SHALE (SLIGHT OIL SHOW)
4	295	BLACK SHALE	11	711	SANDY SHALE
14	309	LIME	28	739	SHALE
1	310	BLACK SHALE	4	743	SANDY SHALE (VERY SLIGHT OIL SHOW) (NO ODOR)
20	330	SHALE	TD	761	SANDY SHALE
10	340	SAND (DRY) (SHALEY)			
70	410	SHALE			
2	412	SHALE (LIMEY)			
7	419	SANDY SHALE			
21	440	SHALE			
2	442	RED BED			
9	451	SHALE			
1	452	SAND (ODOR) (LIMEY)			
5	457	OIL SAND (FAIR BLEED)			
1	458	LIME (ODOR)			
1	459	SHALE (OIL SAND STREAK)			
5	464	SHALE			
12	476	LIME			
35	511	SHALE			
2	513	COAL			
3	516	SHALE			
10	526	LIME			SET SURFACE - 4:00 PM - 12/03/2013
11	537	SHALE			CALLED IN - 12:30 PM - TALKED TO BROOKE
3	540	LIME			WELL TD - 761' FT.
2	542	BLACK SHALE			PLUGGED BACK TO 640' FT.
8	550	DARK SHALE			SET 626' FT. OF 2 7/8" 8 ROUND PIPE - 11:30 AM
10	560	SHALE (LIMEY)			CALLED IN - 10:15 AM - 12/05/2013 - TALKED TO BROOKE
14	574	SHALE			
4	578	LIME (SHALEY)			





MOSSMAN
LUMBER
COMPANY
 1/2 Mile North of Louisburg
 27295 Metcalf Rd.
 P.O. Box 729
 Louisburg, Kansas 66053
 913-837-2955 • 1-800-521-1764

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
221		27109	PO # 27109 ORDER # 7701	NET 10TH	RR	12/4/13	8:08

SOLD TO
 BROADWAY
 20005 WILLOWBERRY ROAD
 LOUISBURG, MO 66053

SHIP TO
 27295 METCALF VALLEY ROAD
 1/2 MILE WEST SOUTH SIDE

DEL. DATE: 11/27/13 TERM: W51
 BLSPR: RR ROBERT RAND
 TAX : 001 LOUISBURG, MO
 DOC# 178855
 * INVOICE *
 ORDR 77016

QUANTITY		UM	SKU	DESCRIPTION	UNITS	PRICE/PER	EXTENSION
SHIPPED	ORDERED						
		EA	PLYWOOD	800 BX FLY PLY	240	3.20 /EA	1,248.00
		EA	PORTLAND	94# PORTLAND CEMENT 1/11	280	9.00 /EA	2,520.00
		EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00
		EA	WRAP	CURTAIN WRAPPED PALLET	14	5.00 /EA	70.00
		EA	FUEL	FUEL SURCHARGE	1	48.55 /EA	48.55
				TONY 913-258-0874			

*Boyscout
K3-13*

** AMOUNT CHARGED TO STORE ACCOUNT **					4,451.14	TAXABLE	4096.55
						NON-TAXABLE	0.00
						SUBTOTAL	4096.55
RECEIVED BY						TAX AMOUNT	354.59
						TOTAL AMOUNT	4451.14