


Lease:	Boyscout	
Owner:	Bobcat Oilfield Services, Inc.	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 662' 2 7/8 8 RD PIPE	Cemented: 80 Sacks of Cement	Hole Size: 5 5/8"



Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056  
Cell # 620-363-2683  
Office # 913-795-2991

Well #: H8-13
Location: NE, SW, NW, NW: S14-T17-R21E
County: MIAMI
FSL: 4436' FT.
FEL: 4627' FT.
API#: 15-121-29703-00-00
Started: 12-10-2013
Completed: 12-12-2013

SN: 621' FT.	Packer: NONE	TD: 801' FT.
Plugged:	Bottom Plug: 10 Sacks 801' FT. TO 670' FT.	

## Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOP SOIL	2	543	COAL
6	7	CLAY	10	553	SHALE
14	21	LIME	7	560	LIME
5	26	SHALE	14	574	SHALE
2	28	RED BED	3	577	LIME
8	36	SHALE	13	590	SHALE
4	40	SAND (DRY)	3	593	LIME
5	45	SHALE	18	611	SHALE
11	66	LIME	4	615	LIME
17	83	SAND (DRY)	3	618	BLACK SHALE
70	153	SHALE	3	621	SHALE (LIME STREAK)
18	171	LIME	5	626	LIME (ODOR)
5	176	SHALE	5	631	SHALE
12	188	SAND (DRY)	2	633	SANDY SHALE (OIL SAND STREAK)
10	198	SHALE	5	638	OIL SAND (GOOD BLEED)
6	204	LIME	1	639	OIL SAND (SHALEY) (GOOD BLEED)
37	241	SHALE	2	641	OIL SAND (SOME SHALE ) (GOOD BLEED)
17	258	LIME	5	646	SANDY SHALE (OIL SAND STREAK)
12	270	SHALE	58	704	SHALE
27	297	LIME	3	707	SANDY SHALE (ODOR)
2	299	SHALE	28	735	SHALE
2	301	BLACK SHALE	10	745	LIME
4	305	SHALE	4	749	BLACK SHALE
20	325	LIME	2	751	SHALE
5	330	SHALE	4	755	SANDY SHALE
14	344	LIME	1	756	LIME
1	345	BLACK SHALE	5	761	SAND (DRY) (SHALEY)
22	367	SHALE	5	766	SHALE
12	379	SANDY SHALE	30	796	DARY SHALE
69	448	SHALE	TD	801	SHALE
5	453	SAND (DRY)			
18	471	SHALE			
1	472	COAL			SET SURFACE PIPE – 12:30 P M – 12/10/13
1	473	SHALE			CALLED IN – 10:30 A M – TALKED TO MICHELLE
2	475	RED BED			WELL TD 801' FT.
8	483	SHALE			PLUGGED BACK TO 670' FT.
6	489	SANDY SHALE (LIMEY)			SET 662' FT OF 2 7/8" 8 ROUND PIPE – 11:00 AM
2	491	LIME			CALLED IN – 9:40 AM – TALKED TO BROOKE
1	492	LIME (OIL SAND STREAK) (POOR BLEED)			
4	496	OIL SAND (LIMEY) (POOR BLEED)			
2	498	SHALE			
15	513	LIME			
78	541	SHALE			



# MOSSMAN LUMBER COMPANY

1/2 Mile North of Louisburg  
27295 Metcalf Rd.  
P.O. Box 729  
Louisburg, Kansas 66053  
913-837-2955 • 1-800-521-1764

*True Value.*

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
551		27189	PO # 27189 DEC 8 7701	NET 100%	BR	12/ 4/13	0:00

S  
O  
L  
D  
  
T  
O

BOSSCAT ON  
20005 COLUMBIAN ROAD  
LOUISBURG, KS 66053

S  
H  
I  
P  
  
T  
O

20005 COLUMBIAN VALLEY ROAD  
WEST BENTON SIDE

DEL. DATE: 12/27/13 TERM: 551  
CLERK: BR ROBERT RAND  
TAX : 001 LOUISBURG, KS

DOC# 170855  
\*\*\*\*\*  
\* INVOICE \*  
\*\*\*\*\*  
ORDR 77015

QUANTITY		UM	SKU	DESCRIPTION	UNITS	PRICE/PER	EXTENSION
SHIPPED	ORDERED						
		EA	FLY PNH	800 BX FLY PNH	200	3.20 /EA	1,248.00
		EA	PORTLAND	944 PORTLAND CEMENT 1/11	280	3.00 /EA	2,520.00
		EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00
		EA	MAKP	EMPTY WOODEN PALLET	14	5.00 /EA	70.00
		EA	FUEL	FUEL SURCHARGE	1	48.55 /EA	48.55
				TOPY 913-259-0074			

*Boyscout  
H8-13*

** AMOUNT CHARGED TO STORE ACCOUNT **	4,461.14	TAXABLE	4096.55
		NON-TAXABLE	0.00
		SUBTOTAL	4096.55
		TAX AMOUNT	364.59
		TOTAL DUE	4461.14

RECEIVED BY