



BASIC
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET
1718 05514 A

DATE _____ TICKET NO. _____

DATE OF JOB <u>1-10-2012</u> DISTRICT <u>PRATT, Ks.</u>				NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:					
CUSTOMER <u>FG HOLL CO. LLC</u>				LEASE <u>LENKNER</u>		WELL NO. <u>1-29</u>			
ADDRESS				COUNTY <u>BARBER</u>		STATE <u>Ks.</u>			
CITY				STATE					
AUTHORIZED BY				SERVICE CREW <u>LESLEY, LAWRENCE, MARQUEZ</u>					
				JOB TYPE: <u>CNW - 5 1/2" L.S.</u>					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
<u>37586</u>	<u>4</u>					<u>1-10-12</u>			<u>7:30</u>
<u>27463</u>	<u>4</u>					ARRIVED AT JOB			<u>8:30</u>
<u>19432-21010</u>	<u>4</u>					START OPERATION			<u>2:30</u>
						FINISH OPERATION			<u>6:30</u>
						RELEASED			<u>7:30</u>
						MILES FROM STATION TO WELL			<u>20</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP 105	AA2 CEMENT	SK	125		
CP 103	60/40 P22	SK	75		
CC 102	CELL-FLAKE	lb	32		
CC 105	DE-FOAMER	lb	30		
CC 111	SALT	lb	562		
CC 115	GAS-BLOK	lb	118		
CC 129	FLA-322	lb	118		
CC 201	GILSONITE	lb	1625		
CF 607	CATCHDOWN PLUG & BAFFLE, 5 1/2"	EA	1		
CF 1251	AUTO FILL FLOAT SHOE, 5 1/2"	EA	1		
CF 1651	TURBOLIZER, 5 1/2"	EA	6		
CF 1901	BASKET, 5 1/2"	EA	1		
CF 2002	CEM. SCRATCHERS - ROTATING TYPE	EA	30		
CC 154	SUPER FLUSH	GAL	500		
E 100	PICKUP MILEAGE	MI	20		
E 101	HEAVY EQUIPMENT MILEAGE	MI	40		
E 113	BULK DELIVERY CHARGE	TM	183		

CHEMICAL / ACID DATA:			

SUB TOTAL		<u>DLS</u>	
SERVICE & EQUIPMENT	%TAX ON \$		
MATERIALS	%TAX ON \$		
TOTAL			

SERVICE REPRESENTATIVE <u>[Signature]</u>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <u>[Signature]</u>
FIELD SERVICE ORDER NO.	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

Customer FG HOLL CO.	Lease No.	Date 1-10-2012
Lease LENKNER	Well # 1-29	
Field Order # 05514	Station PRATT, KS.	Casing 5 1/2" Depth
Type Job CNW - 5 1/2" L.S.	Formation TD-4950'	County BARBER State Ks.
		Legal Description 29-30-13

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size'	Tubing Size	Shots/Ft		Acid	RATE	PRESS	ISIP	
5 1/2			CMT-	125SK AA2				5 Min.
Depth 4945.12	Depth	From	To	Pre Pad @ 1.43 CUFT ³	Max			10 Min.
Volume 117.69 BBL	Volume	From	To	Pad	Min			15 Min.
Max Press 1500	Max Press	From	To	Frac	Avg			Annulus Pressure
Well Connection P.C.	Annulus Vol.	From	To		HHP Used			Total Load
Plug Depth 4929.95	Packer Depth	From	To	Flush 117 BBL	Gas Volume			

Customer Representative ROB LONG	Station Manager D. SCOTT	Treater K. LESLEY		
Service Units	37586	27463	19832	21010
Driver Names	LESLEY / LAWRENCE MARQUEZ			

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
8:30 AM					ON LOCATION - SAFETY MEETING
12:00 PM					SPOT TRUCKS ON LOCATION
12:30 PM					RUN 5 1/2" x 15.5# CSG.
					TURBO - 2, 3, 4, 5, 6, 7
					BASK - #5
2:20 PM					CSG. ON BOTTOM
2:30 PM					HOOK UP TO CSG. / BREAK CIRC. W/RIG
5:30 PM	300		5	6	H ₂ O AHEAD
5:40 PM	250		12	6	SUPERFLUSH
5:59 PM	250		5	6	H ₂ O SPACER
6:00 PM	250		5	6	MIX 25SK 60/40 P02 SCAV. @ 12.0 PPG
6:04 PM	200		32	6	MIX 125SK AA2 @ 15.0 PPG
6:10 PM					CLEAR PUMP & LINE / DROP PLUG
6:15 PM	0		0	7	START DISPLACEMENT
6:25 PM	200		90	6	LIFT PRESSURE
6:28 PM	500		105	5	SLOW RATE - KICK OUT ROTATION
6:30 PM	1500		117	4	PLUG DOWN - HELD
					CIRC. THRU JOB
			6, 4		PLUG R.H. & N.H.
					JOB COMPLETE,
					THANKS -
					KEVEN LESLEY