



ENTERED

TICKET NUMBER 43320
 LOCATION Eureka
 FOREMAN Rick Ledford

PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT APL #15-001-30584 ✓

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-25-13	1828	Baker # BD-3	4	24	18E	Allen
CUSTOMER <u>Colt Energy Inc.</u>						
MAILING ADDRESS <u>P.O. Box 388</u>						
CITY <u>Iola</u>		STATE <u>KS</u>	ZIP CODE <u>66749</u>			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			<u>520</u>	<u>Chris B.</u>		
			<u>515</u>	<u>Merle</u>		

JOB TYPE L/S 0 HOLE SIZE 6 3/4" HOLE DEPTH 987' CASING SIZE & WEIGHT 4 1/2", 10.5 #/ft
 CASING DEPTH 955' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 13.6 # SLURRY VOL _____ WATER gal/sk 6.5 CEMENT LEFT in CASING 20'
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting - Rig up to 4 1/2" casing w/ wireline. Break circulation w/ fresh water. Run 100# gel-flush, 7 bbl dye water. Mixed 90 # class A cement w/ 2% gel, 1% cacl2, 1% phenoxal. @ 13.6 #/gal. pumped casing out of ground @ 1000 PSI, shut down, switched to water. Slowly get circulation @ 1400 PSI. Pumped cement to pit. Decided to just tack bottom, pumped 300# gel-flush, mixed 60 # class A cement w/ 2% gel, 1% cacl2 + 1% phenoxal @ 13.6 #/gal. Washout pump & lines, release plug. Displace plug to 935' w/ 15 1/4 bbl water. Followed plug w/ wireline. Final pump pressure 400 PSI. Closed well in @ 300 PSI. Good circulation @ all times while cementing.

"Thank You"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	1085.00	1085.00
5406	50	MILEAGE	4.20	210.00
11045	150 #	class A cement	15.70	2355.00
11185	280 #	2% gel	.22	61.60
1102	170 #	1% cacl2	.78	132.60
1107A	150 #	1% phenoxal/w	1.35	202.50
11188	400 #	gel-flush	.22	88.00
5407A	7.05	ten mileage bulk tax	1.41	9.93
4404	1	4 1/2" top rubber plug	47.25	47.25
			subtotal	4655.58
			SALES TAX 7.4%	211.91
			ESTIMATED TOTAL	4867.49

AVIN 3737 260933 7.4%
 AUTHORIZATION R.R. Ledford TITLE _____ DATE 7/25/2013

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 43395
LOCATION Eureka KS
FOREMAN Shannon Felk

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT API #15-001-30584 "Top off"

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-22-13	1828	Baker #BD-3	4	24	18E	Allen
CUSTOMER Colt Energy, Inc			TRUCK #			
MAILING ADDRESS P.O. Box 388			DRIVER		TRUCK #	
CITY Iola			DRIVER		TRUCK #	
STATE KS			DRIVER		TRUCK #	
ZIP CODE 66749			DRIVER		TRUCK #	

JOB TYPE 1" Top outside HOLE SIZE 6 3/4 HOLE DEPTH 108 CASING SIZE & WEIGHT 4 1/2", 10.5 #/ft
CASING DEPTH 952' DRILL PIPE --- TUBING 3/4" Tubing OTHER ---
SLURRY WEIGHT --- SLURRY VOL --- WATER gal/sk --- CEMENT LEFT in CASING ---
DISPLACEMENT --- DISPLACEMENT PSI --- MIX PSI --- RATE ---

REMARKS: Rig up to 3/4" Tubing @ 108', mixed 5KS Class "A" cement w/ 20% gel & brought to surface. Annulus stayed full, Job complete.

"Thanks Shannon & crew"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5609	2 Hours	PUMP CHARGE	210.00	420.00 ✓
5406	50	MILEAGE	4.20	210.00 ✓
11045	25 SKS	Class A cement	15.70	392.50 ✓
1118 B	50 #	gel @ 2%	.22	11.00 ✓
5407	1.17 Tons	Ton mileage bulk Truck	m/c	368.00 ✓
			Sub Total	1401.50
			7.40% SALES TAX	29.86 ✓
			ESTIMATED TOTAL	1431.36 ✓

AVIN 3737
AUTHORIZATION R.A. Felk TITLE 061613 DATE 8/22/2013

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.